

VENICE MARINA HARBOR



FY 2023 MAINTENANCE DREDGING
PROJECT: Mississippi River, Baton Rouge to the Gulf of Mexico, LA.
REACH: Venice Marina Harbor
OPERATIONS MANAGER: Michelle Kornick
PHONE: (504) 862-1842
LOCAL SPONSOR: State of Louisiana
Coastal Zone Management: C20220136

DESCRIPTION OF WORK:

Maintain Government owned Harbor to
-12 feet Mean Low Gulf.

HISTORICAL DREDGING FREQUENCY:

As Needed

LAST DREDGED: 2021

TYPE OF DREDGE: Submersible sand pump

ESTIMATED QUANTITY: 24,000 CY

ESTIMATED COST: \$500,000

ADVERTISE: TBD

OPEN BIDS: TBD

AWARD: TBD

START WORK: TBD

DURATION: 14 Days

DREDGING REACH: Venice Marina Harbor

DISPOSAL AREA: Mississippi River

DISPOSAL TYPE: Open Water

REMARKS:

SEDIMENT CHARACTERISTICS:

Fine Sands, Silt, Clay



DREDGING REACH



PLACEMENT AREA



Fiscal Year	Contract No.	Disposal Area	Dredging Quantity (CY)
2017	GOVT	Mississippi River Open Water	20,000
2019	GOVT	Mississippi River Open Water	21,000
2021	GOVT	Mississippi River Open Water	20,000