

GULF INTRACOASTAL WATERWAY HARVEY LOCK FOREBAY



FY 2017 MAINTENANCE DREDGING

PROJECT: Gulf Intracoastal Waterway
SUBPROJECT: Harvey Lock Forebay
OPERATIONS MANAGER: Victor Landry
PHONE: (504) 862-2407
LOCAL SPONSOR: U.S. Government has sufficient interest

DESCRIPTION OF WORK:

Maintain forebay to -12' MLG (with an additional 3' of advance maintenance)

HISTORICAL DREDGING FREQUENCY: Annually

LAST DREDGED: 2013

TYPE OF DREDGE: Cutterhead

ESTIMATED QUANTITY: 20,000 CY

ESTIMATED COST: \$200,000

ADVERTISE: Jul 2017

OPEN BIDS: TBD

AWARD: TBD

START WORK: TBD

DURATION: 1 days

DREDGING REACH: Harvey Lock Forebay

DISPOSAL AREA: Mississippi River

DISPOSAL TYPE: Open Water

REMARKS: Dredged Material discharged beyond the -55' Depth Contour

NOTE: This work is done as part of the New Orleans Harbor Contract



HARVEY LOCK FOREBAY

Fiscal Year	Disposal Area	Dredging Quantity (CY)
2001	Mississippi River Open Water	22,500
2002	Mississippi River Open Water	6,551
		107,008
2003	NO DREDGING	
2004	Mississippi River Open Water	14,807
2005	Mississippi River Open Water	21,666
2006	NO DREDGING	
2007	Mississippi River Open Water	15,605
2008	Mississippi River Open Water	12,260
2009	NO DREDGING	
2010	Mississippi River Open Water	18,071
2011	Mississippi River Open Water	22,186
2012	NO DREDGING	
2013	Mississippi River Open Water	9,615
2014	NO DREDGING	
2015	NO DREDGING	

