

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT				1. CONTRACT ID CODE J		PAGE OF PAGES 1 6	
2. AMENDMENT/MODIFICATION NO. 0001		3. EFFECTIVE DATE 30-Oct-2005		4. REQUISITION/PURCHASE REQ. NO.		5. PROJECT NO.(If applicable) Dalmado	
6. ISSUED BY USACE, CONTRACTING DIVISION ATTN: CEMVN-CT, ROOM 172 7400 LEAKE AVE. NEW ORLEANS LA 70118-3651		CODE W912P8		7. ADMINISTERED BY (If other than item 6) See Item 6			
8. NAME AND ADDRESS OF CONTRACTOR (No., Street, County, State and Zip Code)				X 9A. AMENDMENT OF SOLICITATION NO. W912P8-06-R-0037			
				X 9B. DATED (SEE ITEM 11) 28-Oct-2005			
				10A. MOD. OF CONTRACT/ORDER NO.			
				10B. DATED (SEE ITEM 13)			
CODE		FACILITY CODE					
11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS							
<input checked="" type="checkbox"/> The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offer <input checked="" type="checkbox"/> is extended, <input type="checkbox"/> is not extended.							
Offer must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended by one of the following methods: (a) By completing Items 8 and 15, and returning _____ copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.							
12. ACCOUNTING AND APPROPRIATION DATA (If required)							
13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS. IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.							
A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.							
B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(B).							
C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:							
D. OTHER (Specify type of modification and authority)							
E. IMPORTANT: Contractor <input type="checkbox"/> is not, <input type="checkbox"/> is required to sign this document and return _____ copies to the issuing office.							
14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.) The above numbered solicitation for New Orleans to Venice Hurricane Protection Levees, Plaquemines Parish, Levee District, Emergency Levee Repairs, Reach B-2, Plaquemines Parish, LA is amended as follows: 1. Add Section 02231 to the Specifications. (SEE ATTACHED) 2. Add "by others" at the end of the 1st sentence in Section 02231, paragraph 3.2.5. 3. Change contract duration to be completed by 1 Dec 2005. 4. Replace Drawing 12 of 12 with the Attached Drawing. PROPOSAL IS DUE 3 NOVEMBER 2005 AT 1:00 P.M (LOCAL TIME, .NEW ORLEANS)							
Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.							
15A. NAME AND TITLE OF SIGNER (Type or print)				16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)			
				TEL: _____ EMAIL: _____			
15B. CONTRACTOR/OFFEROR		15C. DATE SIGNED		16B. UNITED STATES OF AMERICA		16C. DATE SIGNED	
_____ (Signature of person authorized to sign)				BY _____ (Signature of Contracting Officer)		30-Oct-2005	

Section Table of Contents

SECTION 02231 - CLEARING

PART 1	GENERAL	1
1.1	SCOPE	1
1.2	MEASUREMENT AND PAYMENT	1
1.3	QUALITY CONTROL	1
PART 2	PRODUCTS (Not Applicable)	1
PART 3	EXECUTION	1
3.1	GENERAL REQUIREMENTS	1
3.2	CLEARING	2
3.2.1	General	2
3.2.2	Reserved	2
3.2.3	Reserved	2
3.2.4	Vegetation	2
3.2.5	Miscellaneous Structure Foundations and Debris	2
3.2.6	Areas to be Cleared	2
3.2.6.1	General	2
3.2.6.2	Reserved	2
3.2.6.3	Reserved	2
3.2.7	Reserved	3
3.3	RESERVED	3
3.4	DISPOSAL OF DEBRIS	3
3.4.1	General	3
3.4.2	Windrows	3

SECTION 02231 - CLEARING

PART 1 GENERAL

1.1 SCOPE

The work covered by this section consists of furnishing all plant, labor, equipment, and materials, and performing all operations necessary for the clearing of the areas specified herein or indicated on the drawings, and for the removal and disposal of all cleared materials, as specified herein.

1.2 MEASUREMENT AND PAYMENT

No measurement will be made for clearing and vegetation removal. Payment for clearing and vegetation removal will be made at the contract lump sum price for "Clearing". Price and payment shall constitute full compensation for furnishing all plant, labor, material and equipment and performing all operations necessary for clearing and vegetation removal of the areas specified herein or indicated on the drawings, and for removing and disposing of all cleared and vegetation removal materials.

1.3 QUALITY CONTROL

The Contractor shall establish and maintain quality control for clearing operations to assure compliance with contract requirements, and maintain records of its quality control for all construction operations including, but not limited to, the following:

- (1) Clearing. Station to station limits, transverse clearing limits from applicable centerline; percentages of area complete; type of material.
- (2) Reserved.
- (3) Disposition of Cleared Materials. Method and location of disposition; damage to timber or improvements which are not to be cleared.

The original and two (2) copies of these records of inspections and tests, as well as the records of corrective action taken, shall be furnished the Government daily. Format of the report shall be as prescribed in Section 01451, "CONTRACTOR QUALITY CONTROL".

PART 2 PRODUCTS (Not Applicable)

PART 3 EXECUTION

3.1 GENERAL REQUIREMENTS

All clearing work for embankments shall be completed at least 500-feet in advance of embankment construction. If regrowth of vegetation or trees occurs after clearing and before placement of fill, the Contractor will be required to clear the area again prior to embankment construction, and no payment will be made for this additional clearing.

3.2 CLEARING

3.2.1 General

Clearing, unless otherwise specified, shall consist of the complete removal above the ground surface of all trees, stumps, down timber snags, brush, vegetation, loose stone, abandoned structures, fencing and similar debris.

3.2.2 Reserved

3.2.3 Reserved

3.2.4 Vegetation

Vegetation to be removed shall consist of crops, grass, bushes, and weeds. Close-growing grass and other vegetation shall be removed from areas to receive fully compacted fill to provide a complete bare earth surface immediately prior to foundation preparation. Removal of vegetation from the side of existing levees shall be limited to 1,000-feet in advance of embankment placement. Acceptance of the vegetation removal operation shall precede the initiation of foundation preparation in the area from which vegetation has been removed. For areas to receive uncompacted fill, close-growing grass and other vegetation shall be mowed not to exceed 2-inches above the ground surface or existing embankment prior to foundation preparation.

3.2.5 Miscellaneous Structure Foundations and Debris

The Contractor shall also remove all abandoned foundations, debris, and other materials which remain after buildings or other structures have been removed.

3.2.6 Areas to be Cleared

3.2.6.1 General

The entire area to be occupied by the embankment together with strips 5-feet wide contiguous thereto, shall be cleared.

3.2.6.2 Reserved

3.2.6.3 Reserved

3.2.7 Reserved

3.3 RESERVED

3.4 DISPOSAL OF DEBRIS

3.4.1 General


The primary method of disposing of all debris resulting from clearing operations shall be by windrowing adjacent to the landside levee toe. The material resulting from the vegetation removal operations performed on the side of the existing levee shall be stockpiled within the right-of-way limits and be evenly spread over the completed embankments, either compacted or uncompacted, prior to the fertilizing and seeding operation.

3.4.2 Windrows

All debris shall be placed in a windrow adjacent to the landside levee toe.

[illegible]

	LAMBERT COORDINATES (X,Y)
20	2595970.371,253123.921
20	2595559.704,251721.040
20	2595832.796,252471.637
20	2596321.129,253028.205
20	2598681.056,254607.423
20	2599317.706,254785.449
20	2601814.363,254688.519
20	2596825.592,253703.135



1. NOTIFY CONTRACTING OFFICER IF ANY PIPES, DRAINS, OR OTHER SUCH SUBSURFACE FACILITIES ARE ENCOUNTERED DURING EXCAVATION. DO NOT REMOVE OR DISTURB UNTIL SO DIRECTED BY THE CONTRACTING OFFICER.
2. AROUND AREAS WHICH ARE FLOODED FROM STORM WATER SHALL BE DRAINED AS QUICKLY AS POSSIBLE AND KEPT DRY BY DITCHING, SUMP PUMPING, OR OTHER APPROVED METHODS.
3. EXCAVATED MATERIALS SHALL BE STOCKPILED, ALLOWED TO DRAIN, AND PROCESSED ON-SITE IN THE LOCATION SHOWN, BEFORE IT IS HAULED OFF-SITE.
4. BOTTOMS OF EXCAVATED AREAS SHALL BE SMOOTHED AND SLOPED TO DRAIN.
5. DO NOT EXCAVATE, FILL OR DISTURB WITHIN THE SOUTHERN NATURAL GAS PIPELINE EASEMENT, BUFFER AREAS, DESIGNATED ACCESS ROUTES, OR OTHER DESIGNATED EASEMENTS.

FILE
NUMBER
H-8-XXXXX
DWG. 12 OF 12

EVANS-GRAVES ENGINEERS, INC.
ENGINEERING CONSULTANTS