

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT			1. CONTRACT ID CODE	PAGE OF PAGES	
			J	1	7
2. AMENDMENT/MODIFICATION NO. 0003	3. EFFECTIVE DATE 15-Sep-2006	4. REQUISITION/PURCHASE REQ. NO.		5. PROJECT NO.(If applicable) Dalmado	
6. ISSUED BY USACE, CONTRACTING DIVISION ATTN: CEMVN-CT, ROOM 172 7400 LEAKE AVE. NEW ORLEANS LA 70118-3651		CODE W912P8	7. ADMINISTERED BY (If other than item 6) See Item 6		
8. NAME AND ADDRESS OF CONTRACTOR (No., Street, County, State and Zip Code)			<input checked="" type="checkbox"/>	9A. AMENDMENT OF SOLICITATION NO. W912P8-06-R-0194	
			<input checked="" type="checkbox"/>	9B. DATED (SEE ITEM 11) 18-Aug-2006	
				10A. MOD. OF CONTRACT/ORDER NO.	
				10B. DATED (SEE ITEM 13)	
CODE	FACILITY CODE				
11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS					
<input checked="" type="checkbox"/> The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offer <input checked="" type="checkbox"/> is extended, <input type="checkbox"/> is not extended.					
Offer must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended by one of the following methods: (a) By completing Items 8 and 15, and returning _____ copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.					
12. ACCOUNTING AND APPROPRIATION DATA (If required)					
13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS. IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.					
A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.					
B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(B).					
C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:					
D. OTHER (Specify type of modification and authority)					
E. IMPORTANT: Contractor <input type="checkbox"/> is not, <input type="checkbox"/> is required to sign this document and return _____ copies to the issuing office.					
14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.) The above numbered solicitation for West Bank and Vicinity, New Orleans, Louisiana, Hurricane Protection Project, Lake Cataouatche Levee Enlargement, Hwy 90 to Pump Station, Baseline Station 156+48 to 308+00 is amended as shown on the attached pages. (See Attached) PROPOSAL DUE DATE PROPOSALS ARE DUE ON 22 SEPTEMBER 2005, 2:00 P.M. LOCAL TIME AND PLACE, NEW ORLEANS, LA.					
Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.					
15A. NAME AND TITLE OF SIGNER (Type or print)			16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)		
			TEL: _____ EMAIL: _____		
15B. CONTRACTOR/OFFEROR _____ (Signature of person authorized to sign)	15C. DATE SIGNED	16B. UNITED STATES OF AMERICA BY _____ (Signature of Contracting Officer)		16C. DATE SIGNED 15-Sep-2006	

SECTION 00010

Delete pages 00010-3 and 00010-4 in their entirety and substitute the attached pages 00010-3 and 00010-4 therefore.

SECTION 00700

Page 13, paragraph 52.211-12 LIQUIDATED DAMAGES—CONSTRUCTION (SEP 2000). Change "\$1,750.00" to "\$4,800.00".

SECTION 02231

Page 3, paragraph 3.2.6.3. Add the following to the end of the paragraph: "The Contractor shall clear all lands starting from the levee protected side berm toe, to the protected side R/W limits from B/L Sta. 157+21 to B/L Sta. 212+53."

Page 4. Add the following new paragraph after paragraph 3.3.2.2:

"3.3.2.3 Other Areas

The Contractor shall grub all lands starting from the levee protected side berm toe to the protected side R/W limits from B/L Sta. 157+21 to B/L Sta. 212+53."

SECTION 02332

Page 11, the 2nd paragraph labeled 3.1.1, and paragraph 3.1.2. Renumber as "3.1.2" and "3.1.3" respectively.

Page 12, paragraph 3.2.3. Add the following as the next to last sentence of this paragraph:

"The Contractor may remove and dispose soft soil mud/wave materials in fully exhausted portions of the borrow pit or he/she may spread evenly and sufficiently to slope to drain between the protected side levee berm toe and the new drainage canal/borrow pit. The materials shall be spread not to exceed a height of 4 feet and be no closer than 40 feet to the cut for the new drainage canal or borrow pit. The Contractor shall remove all soft soil mud/wave materials from the levee and berm footprint."

SECTION 02731

Page 2, paragraph 1.3.2. Delete this paragraph in its entirety and substitute the following therefore:

“1.3.2 Granular Fill for the Existing Drainage Canal

Measurement for granular fill used for filling the existing drainage canal will be made by the cubic yard in approved vehicles at the site of the work. Allowance will not be made for wastage or shrinkage during transportation from car or other point of loading. Approved vehicles for this purpose may be of any type acceptable to the Contracting Officer. The body shall be that of any shape that the actual delivered contents may be readily and accurately determined and will remain constant. Unless all approved vehicles for the work are of uniform capacity, each vehicle must bear a plainly legible identification mark indicating its approved capacity. The Government may reject all loads hauled in non-approved vehicles. Upon delivery of each load at the jobsite and prior to the Contractor’s measurement of each load, the Contractor shall “level-off” each load within the approved vehicles so that an accurate measurement of each load can be made. The on-site measurement location shall be coordinated with and approved by the Contracting Officer. After leveling off the load, the Contractor’s Quality Control personnel shall measure each load at the site of work. The Government will inspect each load, check its yardage and witness the Contractor’s measurement of each load.”

Page 3, paragraph 1.4.2. In the 2nd line, change “ton” to “cubic yard”. Starting in the 5th line, delete “including all costs for furnishing and maintaining the certified scales and weighing for measurements;”.

Page 3, subparagraph 1.5.1 (1)(a)2. Testing. In the 5th line, change “3,000 tons” to “2,000 cubic yards”.

Page 6, paragraph 2.2. Change “non-plastic and siliceous sand” to “gravel and crushed stone (excluding recycled concrete)”.

DRAWINGS

Sheet Identification Number 2.

NOTE 11. Add the following to this note:

“THE DITCH INVERT AT THE PROTECTED SIDE BERM TOE SHALL BE AT ELEVATION -9.0 AND SLOPED TO DRAIN TO THE NEW DRAINAGE CANAL/BORROW PIT AT INVERT ELEVATION -10.0. THE DITCH CROSS SECTION SHALL HAVE A 2 FOOT WIDE FLAT BOTTOM WITH NO STEEPER THAN 1V ON 2 H SIDE SLOPES.

NOTE 12. Add the following to this note:

“ADD FILL TO THE PROTECTED SIDE BERM, MAXIMUM 1 FOOT AT THE MID POINT BETWEEN DITCHES IN NOTE 11, AND GRADE, SUFFICIENT TO

SLOPE TO DRAIN, TO PREVENT PONDING AND DIRECT FLOW TO THE TRANSVERSE DITCHES DISCUSSED IN NOTE 11 ABOVE.”

Note located in the upper right hand corner. Change “EVENLY BETWEEN SAME STATIONS” to “EVENLY BETWEEN SAME STATIONS, NOT TO EXCEED 4 FEET AND BE NO CLOSER THAN 40 FEET FROM THE CUT OF THE DRAINAGE CANAL.”

Sheet Identification Number 3.

Note located in the upper left hand corner. Change “EVENLY BETWEEN SAME STATIONS” to “EVENLY BETWEEN SAME STATIONS, NOT TO EXCEED 4 FEET AND BE NO CLOSER THAN 40 FEET FROM THE CUT OF THE DRAINAGE CANAL.”

Sheet Identification Number 4.

Reverse set of arrow heads at the DETAIL A(on Drawing 4, Located Drawing 8).

Sheet Identification Number 5.

- a. Under CONSRUCTION PHASING, Reverse the labels of areas denoted as PHASE 3 and PHASE 4 located at the right hand side of the drawing (and to the floodside of the levee B/L and C/L).
- b. At 6 locations, change reference to settlement gages on drawing 14 and correct note to read SEE DWG. 13.
- c. Correct settlement gages locations shown at the bottom of the existing drainage canal to be located at the interface between the granular fill and the uncompacted fill at these same three areas.

Sheet Identification Number 9.

NOTE 1. Delete this note in its entirety and replace with “NOTE 1. RESERVED” therefore.

TYPICAL SECTION, REQUIRED NEW DRAINAGE CANAL EXCAVATION.

(1) Change “MANDATORY DRY EXCAVATION”, to “MAXIMUM DRY EXCAVATION 12 FEET”

(2) Change “MINIMUM CANAL POOL ELEVATION FOR MANADATORY WET EXCAVATION” TO “MINIMUM CANAL POOL ELEVATION FOR WET EXCAVATION”

Sheet Identification Number 10.

At the "NEW ACCESS ROAD" detail (upper right side of page), change "3' CUT" to "3" CUT".

At the "TYPICAL PIPE ENDS SECTION" add to call out 72" CMP (TYP), "10 GAGE MINIMUM WALL THICKNESS".

Sheet Identification Number 11.

Correct CHART, "TABULATION – RIGHT OF WAY", as follows;

Starting at P.I. 15 and ending at P.I 29, change OFFSET from 900' to 1050'.

SECTION 00010 - BIDDING SCHEDULE (Government Provided Duration)
Project shall be complete in 434 calendar days after the date of Notice to Proceed.

West Bank and Vicinity, New Orleans, Louisiana, Hurricane Protection Project
 Lake Cataouatche Levee Enlargement, Lake Cataouatche Hwy 90 to
 Pump Station, Baseline Station 156+48 to 308+00, Jefferson Parish, Louisiana

Item	Description	Estimated Quantity	Unit	Unit Price	Estimated Amount
0001	Mobilization and Demobilization	1	LS		
0002	Truck Wash-Down Rack	1	LS		
0003	Clearing and Grubbing	1	LS		
0004	Borrow Pit Development	1	LS		
0005	New Drainage Canal Excavation	1	LS		
0006	New Access Road	1	LS		
0007	New Drainage Canal Maintenance	1	LS		
0008	Security Fencing-Gate	1	LS		
0009	Security Fencing-Chain Link	50	LF		
0010	Granular Fill				
*0010AA	First 262,500	262,500	CY		
*0010AB	All Over 262,500	175,000	CY		
0011	Embankment -Compacted Fill				
0011AA	First 120,000	120,000	CY		
0011AB	All Over 120,000	90,000	CY		
0012	Embankment - Uncompacted Fill				
0012AA	First 330,000	330,000	CY		
0012AB	All Over 330,000	220,000	CY		
0013	New Ramp and Turn Around	1	LS		
0014	Levee Markers and Pads	1	LS		
0015	Permanent Culvert Crossing	1	LS		
0016	Fertilizing, Seeding and Mulching	125	Acre		
0017	Timber Bridge Mat at B/L Sta. 120+83	1	LS		
0018	Timber Bridge Mat at New Access Road C/L Sta. 0+52	1	LS		

TOTAL: \$

*Denotes a change from the previous Bidding Schedule

SECTION 00010 – OPTIONAL BIDDING SCHEDULE (Compressed Performance Period)

Project shall be complete in _____ calendar days after the date of Notice to Proceed.

West Bank and Vicinity, New Orleans, Louisiana, Hurricane Protection Project
 Lake Cataouatche Levee Enlargement, Lake Cataouatche Hwy 90 to
 Pump Station, Baseline Station 156+48 to 308+00, Jefferson Parish, Louisiana

Item	Description	Estimated Quantity	Unit	Unit Price	Estimated Amount
0001	Mobilization and Demobilization	1	LS		
0002	Truck Wash-Down Rack	1	LS		
0003	Clearing and Grubbing	1	LS		
0004	Borrow Pit Development	1	LS		
0005	New Drainage Canal Excavation	1	LS		
0006	New Access Road	1	LS		
0007	New Drainage Canal Maintenance	1	LS		
0008	Security Fencing-Gate	1	LS		
0009	Security Fencing-Chain Link	50	LF		
0010	Granular Fill				
*0010AA	First 262,500	262,500	CY		
*0010AB	All Over 262,500	175,000	CY		
0011	Embankment -Compacted Fill				
0011AA	First 120,000	120,000	CY		
0011AB	All Over 120,000	90,000	CY		
0012	Embankment - Uncompacted Fill				
0012AA	First 330,000	330,000	CY		
0012AB	All Over 330,000	220,000	CY		
0013	New Ramp and Turn Around	1	LS		
0014	Levee Markers and Pads	1	LS		
0015	Permanent Culvert Crossing	1	LS		
0016	Fertilizing, Seeding and Mulching	125	Acre		
0017	Timber Bridge Mat at B/L Sta. 120+83	1	LS		
0018	Timber Bridge Mat at New Access Road C/L Sta. 0+52	1	LS		

TOTAL: \$

*Denotes a change from the previous Bidding Schedule