

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT			1. CONTRACT ID CODE	PAGE OF PAGES
2. AMENDMENT/MODIFICATION NO. 0002			3. EFFECTIVE DATE 08-Aug-2004	4. REQUISITION/PURCHASE REQ. NO.
6. ISSUED BY AFGHANISTAN ENGINEER DISTRICT US ARMY CORPS OF ENGINEERS KABUL APO AE 09356			7. ADMINISTERED BY (If other than item 6) <b>See Item 6</b>	5. PROJECT NO.(If applicable)
8. NAME AND ADDRESS OF CONTRACTOR (No., Street, County, State and Zip Code)			<input checked="" type="checkbox"/> 9A. AMENDMENT OF SOLICITATION NO. W917PM-04-R-0012	<input checked="" type="checkbox"/> 9B. DATED (SEE ITEM 11) 28-Jul-2004
CODE			10A. MOD. OF CONTRACT/ORDER NO.	
FACILITY CODE			10B. DATED (SEE ITEM 13)	
11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS				
<input checked="" type="checkbox"/> The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offer <input type="checkbox"/> is extended, <input checked="" type="checkbox"/> is not extended. Offer must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended by one of the following methods: (a) By completing Items 8 and 15, and returning _____ copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.				
12. ACCOUNTING AND APPROPRIATION DATA (If required)				
13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS. IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.				
A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.				
B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(B).				
C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:				
D. OTHER (Specify type of modification and authority)				
E. IMPORTANT: Contractor <input type="checkbox"/> is not, <input type="checkbox"/> is required to sign this document and return _____ copies to the issuing office.				
14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.) Amendment 2				
Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.				
15A. NAME AND TITLE OF SIGNER (Type or print)			16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)	
			TEL: _____ EMAIL: _____	
15B. CONTRACTOR/OFFEROR  _____ (Signature of person authorized to sign)		15C. DATE SIGNED	16B. UNITED STATES OF AMERICA  BY _____ (Signature of Contracting Officer)	16C. DATE SIGNED  08-Aug-2004

## SECTION SF 30 BLOCK 14 CONTINUATION PAGE

**SUMMARY OF CHANGES**

(End of Summary of Changes)

**The following items are applicable to this modification:**CHANGES TO RFP

CONTRACT W917PM-04-R-0012  
DESIGN AND CONSTRUCTION OF THE REHABILITATION OF THE KANDAHAR AIRFIELD (KAF)  
KANDAHAR, AFGHANISTAN

## CHANGES TO RFP

**SPECIFICATION SECTION 00801, SPECIAL CONTRACT REQUIREMENTS**

1. In paragraph 10, **DELETE** the following:

60 Days 0003 Runway Repair Phase 1 \$200  
60 Days 0004 Runway Repair Phase 2 \$200  
90 Days 0005 Runway Repair Phase 3 \$200  
90 Days 0006 Runway Repair Phase 4 \$200  
365 Days 0007 Airfield Lighting and NAVAIDS \$200

**REPLACE** with:

120 Days 0003 Runway Repair Phase 1 \$200  
120 Days 0004 Runway Repair Phase 2 \$200  
120 Days 0005 Runway Repair Phase 3 \$200  
120 Days 0006 Runway Repair Phase 4 \$200  
480 Days 0007 Airfield Lighting and NAVAIDS \$200

**SPECIFICATION SECTION 0802, SPECIAL CLAUSES**

1. In paragraph 1.64.1.1, **DELETE** the entire paragraph, and **REPLACE** with:

Kandahar Airfield has had surface UXO and mine clearing by an Army Explosive Ordnance Disposal (EOD) team. However, unexploded ordnance (UXO) subsurface clearing for heavy equipment operations and for over-excavation for pavement sections will require the contractor to perform UXO and mine surveillance. This applies to all construction and staging areas. The runway, approach lights areas, taxiways, and aprons will require UXO subsurface clearing in areas where new work is constructed. It is assumed that areas where old pavement is demolished and replaced there is no UXO (under the old pavement). Contractor's camp, bulk materials storage areas, equipment storage areas, etc. will also require surface and/or subsurface UXO clearing based on locations of batch plant, bulk storage areas, etc. For any and all areas on the air base, it is the responsibility of the Contractor to be aware of the risk of encountering UXO and to take all actions necessary to assure a safe work area to perform the requirements of this contract. If at any time during contract performance, the Contractor becomes aware of or

encounters UXO or potential UXO, even after clearing has been accomplished, the Contractor shall immediately stop work at the site of the encounter, move to a safe location, notify the Contracting Officer, and mitigate any delays to scheduled or unscheduled contract work. The Contractor assumes the risk of any and all personal injury, property damage or other liability, arising out of and resulting from any Contractor action hereunder. In any case the Contractor shall be responsible for identifying UXO and mines. The Government shall be responsible for clearing UXO.

For any staging area located outside the perimeter fence, the Contractor will be responsible for clearing the area of UXO and mines.

2. In paragraph 1.64.5, **DELETE** the entire paragraph, and **REPLACE** with:

The Contractor shall have a UXO Team which shall monitor all excavation activities in areas potentially contaminated with UXO. Any excavation below 152 mm (6 inches) shall be closely monitored by the UXO Team and/or UXO specialist. One member of the team shall be positioned to the rear and upwind of the excavation equipment for continuous visual observation of activities. If the construction contractor unearths or otherwise encounters suspect UXO, all excavation activities shall cease. The UXO team will assess the condition of the UXO to determine if disposal action is required. Once the UXO has been encountered in an excavation, no further excavation is allowed at that location. Once the UXO has been removed and the UXO team has issued the "All Clear" signal, excavation may continue.

## **SPECIFICATION SECTION 01010, SCOPE OF WORK**

1. In paragraph 1.1, in the second paragraph, **DELETE** the sentence:

For the reconstruction of main and hangar aprons Contractor shall replace approximately 177,477 square meters of aprons with PCC pavement.

**REPLACE** with the sentence:

For the reconstruction of main and hangar aprons Contractor shall replace approximately 50,134 square meters of aprons with PCC pavement.

2. In paragraph 1.3, **DELETE** the sentence:

All base work shall be completed within 365 calendar days.

**REPLACE** with the sentence:

All base work shall be completed within 480 calendar days.

3. In paragraph 1.5.1, **DELETE** the sentence:

Phase I shall be completed within 60 days, phase II within 60 days, phase III within 90 days, and phase IV within 90 calendar days.

**REPLACE** with the sentence:

Phase I shall be completed within 120 days, phase II within 120 days, phase III within 120 days, and phase IV within 120 calendar days.

4. In paragraph 1.5.2.1, **ADD**:

The amount of slab repair shall be approximately 1,000 square meters.

5. In paragraph 1.5.2.2, **ADD**:

The amount of slab repair shall be approximately 1,000 square meters.

6. In paragraph 1.5.2.5, **DELETE** the sentence:

For the reconstruction of main and hangar aprons Contractor shall replace approximately 177,477 square meters of aprons with PCC pavement.

**REPLACE** with the sentence:

For the reconstruction of main and hangar aprons Contractor shall replace approximately 50,134 square meters of aprons with PCC pavement.

7. In paragraph 1.5.2.5, **ADD** the sentence:

The thickness of the aprons is the same as touchdown areas.

## **SPECIFICATION SECTION 169991, TECHNICAL REQUIREMENTS**

1. In paragraph 1.2, **DELETE** the paragraph:

It is the responsibility of the Contractor to be aware of the risk of encountering UXO and to take all actions necessary to assure a safe work area to perform the requirements of this contract. If at any time during contract performance, the Contractor becomes aware of or encounters UXO or potential UXO, the Contractor shall immediately stop work at the site of the encounter, move to a safe location, notify the Contracting Officer, and

mitigate any delays to scheduled or unscheduled contract work. The Contractor shall remove and dispose of UXOs. The Contractor assumes the risk of any and all personal injury, property damage or other liability, arising out of and resulting from any Contractor action hereunder. In these cases the contractor shall be required to identify and dispose of the ordnance.

**REPLACE** with the paragraph:

For all activities on the Kandahar Airfield property, it is the responsibility of the Contractor to be aware of the risk of encountering UXO and to take all actions necessary to assure a safe work area to perform the requirements of this contract. If at any time during contract performance, the Contractor becomes aware of or encounters UXO or potential UXO, even after clearing has been accomplished, the Contractor shall immediately stop work at the site of the encounter, move to a safe location, notify the Contracting Officer, and mitigate any delays to scheduled or unscheduled contract work. The Contractor assumes the risk of any and all personal injury, property damage or other liability, arising out of and resulting from any Contractor action hereunder. In any case the Contractor shall be responsible for identifying UXO and mines. The Government shall be responsible for clearing UXO.

2. In paragraph 1.6, **DELETE** reference to “Section 01060.” And **REPLACE** with “Section 0802.”

3. In paragraph 1.8.4.3 (a), **DELETE** the sentences:

Runway Overlay. The entire area of runway to be overlaid shall be cleaned with a power broom to remove foreign matter. The minimum overlay thickness shall be as shown in Table 2.

**REPLACE** with the sentence:

Runway Reconstruction. The minimum pavement thickness shall be as shown in Table 2.

4. In paragraph 1.8.4.3, **DELETE** the paragraph:

c. Runway Overruns. Paved overruns, 60 m long, are required off of each threshold. Shoulders shall be constructed per the UFC 3-260-01. The minimum pavement thicknesses shall be as shown in Table 2 “Minimum Pavement Thicknesses.”

5. In paragraph 1.8.4.4, **DELETE** reference to “ACC” and **REPLACE** with “AC.”

6. In paragraph 1.8.4.4, **DELETE** the sentence:

For the rehabilitation of taxiways A and E PPC pavement shall be overlaid following tack coat application.

**REPLACE** with the sentences:

For the rehabilitation of taxiways A and E contractor shall clean joints and seal and remove slab sections that have failed. Tack coat application shall be applied on PCC pavement.

7. In paragraph 1.8.4.5, **DELETE** the sentence:

Approximately 177,477 square meters of existing aprons shall be replaced with PCC pavement.

**REPLACE** with the sentence:

Approximately 50,134 square meters of existing aprons shall be replaced with PCC pavement.

8. In paragraph 1.8.6.2, **DELETE** the sentence:

All excavated material, except clean material needed for pavement edge backfill, shall be removed and disposed of at a site provided by the Government on base property.

**REPLACE** with the sentence:

All excavated material, except clean material needed for pavement edge backfill, shall be removed and disposed of at a site approved by the Contracting Officer.

9. In paragraph 1.8.7.1, **DELETE** reference to “Specification Section 02300.” And **REPLACE** with “Specification Section 169992.”

## **SPECIFICATION SECTION 169994, SUBBASE COURSES**

1. In paragraph 3.3, **DELETE** references to “Section 02300: EARTHWORK.” And **REPLACE** with “Section 169992: EARTHWORK.”