

## FY 2014 MAINTENANCE DREDGING

**PROJECT:** Gulf Intracoastal Waterway  
**SUBPROJECT:** BAYOU PEROT  
**PROJECT MANAGER:** Victor Landry  
**PHONE:** (504) 862-2407  
**LOCAL SPONSOR:** U.S. Government has sufficient interest

### DESCRIPTION OF WORK:

Maintain 12' x 125' channel (with an additional 3' of advance maintenance)

**HISTORICAL DREDGING FREQUENCY:** As Needed  
**LAST DREDGED:** 1995  
**TYPE OF DREDGE:** Cutterhead  
**ESTIMATED QUANTITY:** 200,000 CY  
**ESTIMATED COST:** \$1,000,000

**ADVERTISE:** May 2014  
**OPEN BIDS:** TBD  
**AWARD:** TBD  
**START WORK:** TBD  
**DURATION:** 14 days

**DREDGING REACH:** GIWW Mile 19-21  
**DISPOSAL AREA:** Bayou Perot Site  
**DISPOSAL TYPE:** Open Water  
**REMARKS:** Wetlands Restoration

## GULF INTRACOASTAL WATERWAY BAYOU PEROT



**PROJECT AUTHORITY:** The 384-mile-long GIWW was authorized by the Rivers and Harbors Acts of 1946 and 1962, and provides for a navigational channel across the State of Louisiana from the Rigolets in Lake Borgne to the Sabine River. A 12-foot-deep by 150-foot-wide channel is maintained in the first 33 miles from the Rigolets to New Orleans, Louisiana, and a 12-foot-deep by 125-foot-wide waterway is provided in the remainder of the mainstem.

# Beneficial Use of Dredged Material GIWW – BAYOU PEROT

Fiscal Year	Disposal Area	Dredging Quantity (CY)	Acres
1995	Beneficial Use Area A	157,757	20
1996-2012	NO DREDGING		

