

FY 2014 MAINTENANCE DREDGING

PROJECT: Mississippi River
SUBPROJECT: Outlets At Venice
REACH: Tiger Pass
PROJECT MANAGER: Donald Schneider
PHONE: (504) 862-1828
LOCAL SPONSOR: Plaquemines Parish, LA

DESCRIPTION OF WORK:

Maintain a -14' x 250' channel from Mile 67.0 to 14.0, and a 16' x 250' channel in the jetty and bar channel (with an additional 2' of advance maintenance.)

HISTORICAL DREDGING FREQUENCY: 2 to 4 years

LAST DREDGED: 2012

TYPE OF DREDGE: Cutterhead

ESTIMATED QUANTITY: 1,000,000 to 2,000,000 CY

ESTIMATED COST: \$3,000,000 - \$7,000,000

ADVERTISE: April 2014

OPEN BIDS: May 2014

AWARD: May 2014

START WORK: Jun 2014

DURATION: Approximately 90 days for contract

DREDGING REACH: Tiger Pass

DISPOSAL AREA: Adjacent to channel

DISPOSAL TYPE: Open Water

REMARKS: Wetland Development

MISSISSIPPI RIVER, OUTLETS AT VENICE, TIGER PASS



PROJECT AUTHORITY: The River and Harbor Act of 1968, approved 13 August 1968 (House Document 361, 90th Congress, 2nd Session), provides for additional navigation outlets from the Mississippi River in the vicinity of Venice, Louisiana, by enlargement of the existing channels of Baptiste Collette Bayou and Grand Tiger Passes to provide channels 14 feet deep (Mean Low Gulf) over a bottom width of 150 feet, with entrance channels in open water 16 feet deep over a bottom width of 250 feet. Jetties, to the 6-foot depth contour, are authorized if and when justified to reduce the cost of maintenance.

BENEFICIAL USE OF DREDGED MATERIAL TIGER PASS

Fiscal Year	Contract No.	Disposal Area	Dredging Quantity (CY)	Acres
2000-2001	NO DREDGING			
2002	C-0067	WD	1,658,940	25
2003-2004	NO DREDGING			
2005	C-0011	WD	1,565,868	30
2006	C-0143	WD	2,387,500	88
2007-2008	NO DREDGING			
2009	C-0028	WD	2,148,270	24
2010	C-0124	WD	1,779,723	50
2011	NO DREDGING			
2012	C-0024	WD	2,413,042	126

WD= Wetlands Development

