05. LOCKS (75' x 1200')

Care and Diversion of Water	QUANTY	UOM	CREW ID	OUTPUT	LABOR	EQUIPMNT	MATERIAL	MISC	TOTAL COST	UNIT
Care and Diversion of Water										
Fert, Seed & Mulch					0.00	0.00	0.00	1200.00	1200.00	
	3.00	ACR		0.00	0	0	0	3,600	3,600	1200.00
Seeding, Fertilizing, and Mulch	3.00	ACR			0	0	0	3,600	3,600	1200.00

05. LOCKS (75' x 1200')

Care and Diversion of Water	QUANTY	UOM	CREW ID	OUTPUT	LABOR	EQUIPMNT	MATERIAL	MISC	TOTAL COST	UNIT
Semicompacted fill					0.73	1.60	0.00	0.00	2.33	
	53900	CY	ZAJCLAYEMB	140.00	39,347	86,116	0	0	125,463	2.33
safety & misc					0.00	0.00	0.00	3897.00	3897.00	
	1.00	LS		0.00	0	0	0	3,897	3,897	3897.00
Backfill - Semicompacted	53900	CY			39,347	86,116	0	3,897	129,360	2.40

05. LOCKS (75' x 1200')

Care and Diversion of Water	QUANTY	UOM	CREW ID	OUTPUT	LABOR	EQUIPMNT	MATERIAL	MISC	TOTAL COST	UNIT
dewatering					0.00	0.00	0.00	3304348	3304347.83	
	1.00	LS		0.00	0	0	0	3,304,348	3,304,348	3304348
Dewatering System					0	0	0	3,304,348	3,304,348	

05. LOCKS (75' x 1200')

Care and Diversion of Water	QUANTY	UOM	CREW ID	OUTPUT	LABOR	EQUIPMNT	MATERIAL	MISC	TOTAL COST	UNIT
safety & misc					0.00	0.00	0.00	1304.20	1304.20	
	1.00	LS		0.00	0	0	0	1,304	1,304	1304.20
Excavate and Haul Material					0.39	1.19	0.00	0.00	1.58	
	53900	CY	ZAJJPEXCHL	170.00	20,865	64,071	0	0	84,936	1.58
Cofferdam Removal	53900	CY			20,865	64,071	0	1,304	86,240	1.60
Site Work (Cofferdam)					60,212	150,187	0	3,313,149	3,523,548	
Care and Diversion of Water					60,212	150,187	0	3,313,149	3,523,548	