11. LEVEE AND FLOODWALLS

Floodwalls	QUANTY	UOM	CREW ID	OUTPUT	LABOR	EQUIPMNT	MATERIAL	MISC	TOTAL COST	UNIT
Clearing and Grubbing										
This item is for all equipment, labor, and materials required to clear and grub the area. Heavy clearing is anticipated.										
misc					0.00	0.00	0.00	165.41	165.41	
	1.00	LS		0.00	0	0	0	165	165	165.41
Clearing - Hvy Brush, Avg. Grub					385.77	925.95	0.00	0.00	1311.72	
Med. Trees	2.00	ACR	COMCD	0.40	772	1,852	0	0	2,623	1311.72
Chipping - Hvy. Brush					272.80	332.78	0.00	0.00	605.58	
	2.00	ACR	COMCA	0.28	546	666	0	0	1,211	605.58
Clearing and Grubbing	2.00	ACR			1,317	2,517	0	165	4,000	2000.00

11. LEVEE AND FLOODWALLS

Floodwalls	QUANTY	UOM	CREW ID	OUTPUT	LABOR	EQUIPMNT	MATERIAL	MISC	TOTAL COST	UNIT
Road Surfacing										
This item is for all equipment, labor, and materials required to furnish and place road surfacing materials.										
misc					0.00	0.00	0.00	125.60	125.60	
	1.00	LS		0.00	0	0	0	126	126	125.60
Graded Crushed Agg Rdwy Base Crs					3.04	6.68	17.83	0.00	27.55	
	280.00	CY	XSABA	36.00	851	1,870	4,993	0	7,714	27.55
Road Surfacing	280.00	CY			851	1,870	4,993	126	7,840	28.00
Site Work					2,168	4,388	4,993	291	11,840	
Permanent Access					2,168	4,388	4,993	291	11,840	