







TOTAL PROPWASH REQUIRED FOR ACCESS 38,304 Cu. Yds. (7.60 Acres) MHWL +1.22' NAVD 88 TOTAL CLEANOUT REQUIRES FOR ACCESS 2,756 Cu. Yds. (0.85 Acres) MLWL +0.16' NAVD 88 TOTAL PROPWASH REQUIRED FOR SLIP 6,701 Cu. Yds. (0.83 Acres) TOTAL PROPWASH REQUIRED FOR ROCK PAD 545 Cu. Yds. (0.34 Acres) TOTAL FILL REQUIRED FOR ROCK PAD 545 Cu. Yds. (0.34 Acres) TOTAL FILL REQUIRES FOR SPOIL AREAS 2,756 Cu. Yds. (0.58 Acres) 64' Proposed Spoil 1 MWL +0.7' NAVD 88 Mudline 0.0' NAVD 88 CROSS SECTION F-F' No Scale PLAN VIEW 0.0'NAVD 88 8' Mudline Navigation O Well 힐 TYPICAL ROCK PAD Light No Scale PLAN VIEW Navigation Light if Required

NOTES:

- 1. All structures, facilities, well and pipelines/flowlines occurring in open water areas or in oilfield canals or slips shall be removed within 120 days of abandonment of the facilities for the herein permitted use unless prior written approval to leave such structures in place is received from the Coastal Management Division. This condition does not preclude the necessity for revising the current permit or obtaining a separate Coastal Use Permit, should one be required, for such removal activities.
- 2. As-built drawings shall be submitted within 30 days of completion of this project to the Louisiana Department of Natural Resources, Coastal Management Division, P.O. Box 44487, Baton Rouge, LA 70804-4487 and to Louisiana Land and Exploration Company, P.O. Box 7097, Houma, Louisiana 70361-7097.
- 3. In order to ensure the safety of all parties, the permittee shall contact the Louisiana ONE CALL System (1-800-272-3020), a minimum of 48 hours prior to the commencement of any excavation (Digging, Dredging, Jetting, etc.) or demolition activity.
- 4. Structures will also be marked/lighted in accordance with U.S. Coast Guard regulations.

DISCLAIMER: At this time, Fenstermaker & Associates, Inc. has not performed nor has been asked to perform any type of engineering, hydrological modeling, flood plain, or "No Rise" certification analyses, including but not limited to determining whether the project will impact flood hazards in connection with federal/FEMA, state, and/or local laws, ordinances and regulations. Accordingly, Fenstermaker makes no warranty or representation of any kind as to the foregoing issues, and persons or entities using this information shall do so at their own risk.

TYPICAL 10'x 20' WELL PROTECTOR PLATFORM

To be constructed upon successful

completion of well.

-Centerline of Well

Christmas Tree

No Scale

THE CONTENTS OF THESE PLANS ARE INTENDED EXCLUSIVELY FOR THE PURPOSE OF OBTAINING ENVIRONMENTAL COMPLIANCE PERMITS

0.0' NAVD <u>88</u>

Mudline

MANTI EXPLORATION OPERATING, LLC

PROPOSED PROPWASH, CLEANOUT, ROCK PAD & STRUCTURES

SL 20783 No. 2 Well

Section 32, T21S-R22E

Lafourche Parish, Louisiana



Lafayette New Orleans Houston 135 Regency Sq. Lafayette, LA 70508 Ph. 337-237-2200 Fax. 337-232-3299 www.fenstermaker.com DRAWN BY: JDL PROJ MGR.: RLL REVISED: 06/12/12 JRE

09/27/12 MBD

DATE: 06/07/2012

SHEET 5 OF 5 SHEETS

FILENAME: T:\2012\2124386\DWG\Manti-SL 20783 No.2_COE_PLANS_05-30-2012.dwg