



Permanent Canal Closures & Pumps

Construction Impact Hotline at: 1-877-427-0345

Updated March 2017

U.S. ARMY CORPS OF ENGINEERS

BUILDING STRONG®

Congress has fully authorized and funded the Hurricane and Storm Damage Risk Reduction System (HSDRRS) for southeast Louisiana. The \$14.45 billion HSDRRS includes five parishes, consists of 350 miles of levees and floodwalls; 73 non-Federal pumping stations; 3 canal closure structures with pumps; and 4 gated outlets.

Project Summary / Background

The three main outfall canals in New Orleans are a critical element of the flood control system, serving as drainage conduits for much of the city. The canals run south-to-north near the Orleans Parish lakefront between the Jefferson Parish line and the Inner Harbor Navigation Canal (IHNC) with floodwall-topped levees lining each canal.

The 17th Street Canal extends 13,500 feet from Pump Station 6 to Lake Pontchartrain along the Jefferson Parish line. The Orleans Avenue Canal, between the 17th Street Canal and the London Avenue Canal, runs approximately 11,000 feet from Pump Station 7 to Lake Pontchartrain. The London Avenue Canal extends 15,000 feet north from Pump Station 3 to Lake Pontchartrain about halfway between the Orleans Avenue Canal and the IHNC.

The Corps awarded the approximately \$615 million contract to construct Permanent Canal Closures & Pumps (PCCP) at the mouths of the 17th Street, Orleans Avenue and London Avenue outfall canals on April 17, 2013, to *PCCP Constructors JV*.

The PCCP will provide a permanent and more sustainable measure for reducing the risk of a 100-year level storm surge entering the outfall canals. The PCCP will replace the Interim Closure Structures (ICS), which were constructed in 2006. The notice to proceed was issued on May 6, 2013, and construction will be complete in 2017. The existing Interim Closure Structures will continue to provide 100-year levels of risk reduction until construction of the PCCP is complete.

Project Features

The PCCP will be composed of permanent gated storm surge barriers and brick façade pump stations at or near the lakefront. The pumps will move rainwater out of the canals, around the gates and into Lake Pontchartrain during a tropical weather event, and be equipped with a stand-alone emergency power supply capacity so that it can operate independently of any publically provided utility.

When complete, the PCCP at 17th Street will consist of six 1,800 cubic feet per second (cfs) pumps and two 900 cfs pumps and have a total pumping capacity of 12,600 cfs; the PCCP at Orleans Avenue will consist of three 900 cfs pumps and have a total pumping capacity of 2,700 cfs; the PCCP at London Avenue will consist of four 1,800 cfs pumps and two 900 cfs pumps and have a total pumping capacity of 9,000 cfs.



Rendering of the 17th Street Canal Pump Station



Rendering of the Orleans Avenue Canal Pump Station



Rendering of the London Avenue Canal Pump Station

U.S. ARMY CORPS OF ENGINEERS – TEAM NEW ORLEANS

7400 Leake Avenue, New Orleans, LA 70118 | www.mvn.usace.army.mil

www.facebook.com/permpumps | www.twitter.com/teamneworleans | www.flickr.com/teamneworleans