# Inner Harbor Navigational Canal Lock Replacement- Shallow Draft General Reevaluation Report

## Annex 3: COST ENGINEERING

July 2019

Prepared by MVN EDD Cost Engineering Section

# INNER HARBOR NAVIGATION CANAL LOCK REPLACEMENT SHALLOW DRAFT LOCK FEASIBILITY STUDY

## **COST ENGINEERING APPENDIX**

## Contents

Cost Estimate	2	5
Section 1.	Cost estimate development	5
Section 2.	Estimate Structure:	5
Section 3.	Bid competition:	5
Section 4.	Contract Acquisition Strategy:	5
Section 5.	Labor Shortages:	5
Section 6.	Labor Rates:	5
Section 7.	Materials:	6
Section 8.	Equipment:	6
Section 9.	Fuel:	7
Section 10.	Crews:	7
Section 11.	Unit Prices:	7
Section 12.	Relocation Cost:	7
Section 13.	Mobilization:	7
Section 14.	Field Office Overhead:	7
Section 15.	Overhead assumptions may include:	8
Section 16.	Home Office Overhead:	8
Section 17.	Taxes:	8
Section 18.	Bond:	8
Section 19.	E&D and S&A:	8
Section 20.	Contingencies:	9
Section 21.	Escalation:	9
Section 22.	HTRW:	9
Section 23.	Cost Estimate for the Recommended Plan:	9
Section 24.	Construction Schedule.	9
Total Project	Cost Summary	10
Cost and Sche	edule Risk Analysis (contingency, sensitivity charts)	13
MII Cost Estin	nate	17

Project Construction Schedule	46
Cost and Schodula Rick Analysis (rick register)	10
Cost and Schedule Risk Analysis (risk register)	40

#### **Cost Estimate**

#### Section 1. Cost estimate development

a) The project cost estimate was developed in the MCACES MII cost estimating software and used the standard approaches for a feasibility estimate structure regarding labor, equipment, materials, crews, unit prices, production rates, material quotes, sub and prime contractor markups. This philosophy was taken wherever practical within the time constraints. It was supplemented with estimating information from other sources where necessary such as the 1997 Evaluation Report, recent material quotes, current published estimating information, historic bid data, and updated A/E estimates. The intent was to provide or convey a "fair and reasonable" estimate that depicts the local market conditions. The estimate assumes a typical application of tiering subcontractors for certain project construction features. Given the long span over which this project/program is to be constructed and the unknown economic status during that time, demands from non-governmental civil works projects were not considered to dampen the competition and increase prices.

After the Agency Decision Milestone and during the design of the selected plan (TSP) in early 2019, the MII cost estimate was updated due to the 2 year age limit for the cost estimate. The MII 900' x 110' x 22' cost estimate was fully updated June 2019 incorporating revised quantities prepared and furnished by MVN Engineering Division's Structures Branch and updated material pricing, labor rates, equipment rates, fuel prices, sales tax, markups, etc..

#### Section 2. Estimate Structure:

a) The estimate is structured to reflect the projects performed. The estimate has been subdivided by USACE feature codes that include levees, floodwalls, lock structure, relocations, channels and canals and a bridge.

#### Section 3. Bid competition:

a) It is assumed that there will not be an economically saturated market and that bidding competition will be present.

#### Section 4. Contract Acquisition Strategy:

a) It is assumed that the contract acquisition strategy will be similar to past projects with large unrestricted design/bid/build contracts. There are no declared contract acquisition plan/types at this time.

#### Section 5. Labor Shortages:

a) It is assumed there will be a normal labor market.

#### Section 6. Labor Rates:

a) Local labor market wages are above the local Davis-Bacon Wage Determination and actual rates have been used. This is based upon local information and payroll data received from the New Orleans District Construction Representatives and estimators with experiences in past years.

#### Section 7. Materials:

- a) Cost quotes are used on major construction items when available. Recent quotes may include concrete, steel and concrete piling, rock, gravel, sand, mechanical hydraulic systems, pre-stressed precast concrete bridge girders.
- b) Assumptions include:
  - i) Borrow Materials will be purchased as part of the construction contract. The estimate does anticipate contractor furnished materials for borrow. Prices include delivery of materials
  - ii) Concrete will be purchased from commercial batch plants.
  - iii) Steel Material will be fabricated by know suppliers.
- c) The borrow quantity calculations followed the MVN Geotechnical guidance:
  - i) Hauled Levee: 10 BCY of borrow material = 12 LCY hauled = 8 ECY compacted.
  - ii) An assumed average one-way haul distance of 21 miles was used based upon the local Contractor Furnished pit.
  - iii) Haul speeds are estimated using 40 mph speed average given the long distances and rural areas.
- d) Rock and stone The New Orleans delta area has no rock sources. Historically, rock is transported by barge from northern sources on the Mississippi River. This decision is based upon local knowledge, experience and supported with cost quotes.

#### Section 8. Equipment:

- a) Rates used are based from the latest USACE EP-1110-1-8, Region III. Adjustments are made for fuel and facility capital cost of money (FCCM). Judicious use of owned verses rental rates was considered based on typical contractor usage and local equipment availability. Only a few select pieces of marine \ marsh equipment are considered rental. Full FCCM/Cost of Money rate is latest available; MII program takes EP recommended discount, no other adjustments have been made to the FCCM.
  - i) Trucking: The estimate assumed independent self-employed trucking subcontractors due to the large numbers of trucks required.
  - ii) Dozers: dozers of the D-5/D-6 variety were chosen based on historical knowledge. Heavier equipment gets mired in the mud and soft soils.
  - iii) Rental Rates: Rental rates were used for marsh equipment and select equipment for dredging where rental is typical such as marsh backhoes, tugs, barges.

#### Section 9. Fuel:

a) Fuels (gasoline, on and off-road diesel) were based on local market averages for on-road and off-road for the Gulf Coast area. The Team found that fuels fluctuate irrationally; thus, used an average.

#### Section 10. Crews:

- a) Major crew and productivity rates were developed and studied by senior USACE estimators familiar with the type of work. All of the work is typical to the New Orleans District. The crews and productivities were checked by local MVN estimators, discussions with contractors and comparisons with historical cost data. Major crews include clearing and grubbing, hauling, earthwork, piling and concrete.
- b) Most crew work hours are assumed to be 8 hrs 5 days/wk which is typical to the area.

#### Section 11. Unit Prices:

a) The unit prices found within the various project estimates will fluctuate within a range between similar construction units such as floodwall concrete, earthwork, and piling. Variances are a result of differing haul distances, small or large business markups, subcontracted items, designs and estimates by others.

#### Section 12. Relocation Cost:

a) Relocation costs are defined as the relocation of utilities required for project purposes. In cases where potential significant impacts were known, costs were included within the cost estimate. Costs related to relocations were based upon quantities and utility site location information furnished by MVN Relocations Sections and the information included the utility owner, type of utility, size, location and number of utilities.Pricing was based upon a 2019 utility relocation project within the MVN district which included various types and dimensions of utilities.

#### Section 13. Mobilization:

a) Contractor mobilization and demobilization are based on the assumption that most of the contractors will be coming from within the Gulf Coast/Southern region. Mob/demob costs are based on historical studies of detailed Government estimate mob/demobs. With undefined acquisition strategies and assumed individual project limits for the large number of potential contracts in this program, the estimate mobilization and demobilization is based upon a 2018 MVN mega project which included similar construction scope of work, multiple construction sites and land and marine based construction methods.

#### Section 14. Field Office Overhead:

a) The estimate used a field office overhead rate of 12% for the prime contractors at budget level development. Based on historical studies and experience, Walla Walla District has

recommended typical rates ranging from 7% to 11% for large civil works projects; however, the range does not consider possible incentives such as camps, allowances, travel trailers, meals, etc. which have been used previously to facilitate projects. With undefined acquisition strategies and assumed individual project limits for the multiple number of potential contracts in this program, the estimate utilizes a more comprehensive percentage based approach applied at each contract rather than risking minimizing overhead costs by detailing costs based on an assumed number of contracts. The applied rates were previously discussed among numerous USACE District cost engineers including Walla Walla, Vicksburg, Norfolk, Huntington, St. Paul and New Orleans.

#### Section 15. Overhead assumptions may include:

a) Superintendent, office manager, pickups, periodic travel, costs, communications, temporary offices (contractor and government), office furniture, office supplies, computers and software, as-built drawings and minor designs, tool trailers, staging setup, camp and kitchen maintenance and utilities, utility service, toilets, safety equipment, security and fencing, small hand and power tools, project signs, traffic control, surveys, temp fuel tank station, generators, compressors, lighting, and minor miscellaneous.

#### Section 16. Home Office Overhead:

a) Estimate percentages range based upon consideration of 8(a), small business and unrestricted prime contractors. The rates are based upon estimating and negotiating experience, and consultation with local construction representatives. The applied rates were previously discussed among numerous USACE District cost engineers including Walla Walla, Vicksburg, Norfolk, Huntington, St. Paul and New Orleans.

#### Section 17. Taxes:

a) Local taxes will be applied, using an average between the parishes that contain the work. Reference the LA parish tax rate website: http://www.laota.com/pta.htm

#### Section 18. Bond:

a) Bond is assumed 1% applied against the prime contractor, assuming large contracts.

#### Section 19. E&D and S&A:

- a) USACE Costs to manage design (PED) and construction (S&A) are based on New Orleans District Programmatic Cost Estimate guidance:
  - i) Planning, Engineering & Design (PED): The PED cost includes such costs as project management, engineering, planning, designs, investigations, studies, reviews, value engineering and engineering during construction (EDC). Historically New Orleans District has used an approximate 12% rate for E&D/EDC, applied against the estimated construction costs. Other USACE civil works districts such as St. Paul, Memphis and St. Louis have reported values ranging from 10-15%. Additional costs were added for project management, engineering, planning, designs, investigations, studies, reviews, value engineering. Specific PED costs were originally calculated and then that same percentage was carried forward on all future updates.

ii) Supervision & Administration (S&A): Historically, New Orleans District used a range from 5% to 15% depending on project size and type applied against the estimated construction costs. Other USACE civil works districts such as St. Paul, Memphis and St. Louis report values ranging from 7.5-10%. Consideration includes that a portion of the S&A effort could be performed by contractors. Based on discussions with MVN Construction Division, an S&A cost based on contract durations was developed. Specific S&A costs were originally calculated and then that same percentage was carried forward on all future updates.

#### Section 20. Contingencies:

a) Contingencies were developed using the USACE Cost and Schedule Risk Analysis (CSRA) cost related risks. See summary in Cost Schedule Risk Analysis (CSRA) section.

#### Section 21. Escalation:

a) Escalation used in the TPCS is based upon the US Army Corps of Engineers Engineering Manual (EM) 1110-2-1304 Civil Works Construction Cost Index System (CWCCIS) revised 31 March 2018.

After the Agency Decision Milestone and during the GRR of TSP in early 2019, the MII cost estimate was updated due to the 2 year age limit for the cost estimate. The MII 900' x 110' x 22' cost estimate was updated May 2019 to incorporate the CWCCIS version, 31 March 2018.

#### Section 22. HTRW:

a) The estimate includes no costs for any potential Hazardous, Toxic, and Radioactive Waste (HTRW) concerns. Some material to be removed from the canal is assumed to be contaminated and will be contained in a Confined Disposal Facility (CDF).

#### Section 23. Cost Estimate for TSP:

a) The TSP MII cost estimate was developed during the design of the TSP in early 2019. The costs estimated for the TSP is shown in the section TSP Cost Summary. The project costs include contingency calculated using the USACE MCX Cost and Schedule Risk Analysis program.

#### Schedule 24. Construction Schedule for TSP:

a) The project schedule was developed using the Primavera P6 software and is based on the construction of the individual features of work which includes the dredging of a channel bypass, canal excavation, construction of a cofferdam, the new IHNC lock, a temporary and new bridge for St Claude, demolition of the existing lock and St Claude bridge, earthen levees and floodwalls.

# **Total Project Cost Summary**

PROJECT: New Industrial Canal Lock and Connecting Channels

PROJECT NO: P2 451219

LOCATION: Orleans Parish, Louisiana

This Estimate reflects the scope and schedule in report;

**DISTRICT: New Orleans District** 

PREPARED: 6/13/2019

POC: CHIEF, COST ENGINEERING, John B. Petitbon

**ESTIMATED TOTAL PROJECT COST:** 

\$1,456,613

Civil Works Work Breakdown Structure		ESTIMATED COST				PROJECT FIRST COST (Constant Dollar Basis)				TOTAL PROJECT COST (FULLY FUNDED)					
							F		r (Budget EC): ice Level Date:	2019 1 OCT 18	1				
WBS <u>NUMBER</u> <b>A</b>	Civil Works <u>Feature &amp; Sub-Feature Description</u> <b>B</b>	COST (\$K) <b>C</b>	CNTG (\$K) <b>D</b>	CNTG _(%) <i>E</i>	TOTAL _(\$K)_ <b>F</b>	ESC (%) <b>G</b>	COST _(\$K) <i>H</i>	CNTG _(\$K)/	TOTAL _(\$K) 	Spent Thru: 1-Oct-18 _(\$K)_	TOTAL FIRST COST (\$K) K	INFLATED (%) L	COST (\$K) M	CNTG (\$K) N	FULL _(\$K)_ <i>O</i>
02 05 08 09 11	RELOCATIONS LOCKS ROADS, RAILROADS & BRIDGES CHANNELS & CANALS LEVEES & FLOODWALLS	\$38,825 \$408,274 \$65,773 \$39,826 \$160,231	\$14,365 \$151,061 \$24,336 \$14,736 \$59,285	37.0% 37.0% 37.0% 37.0% 37.0%	\$53,190 \$559,335 \$90,109 \$54,562 \$219,516	0.0% 0.0% 0.0% 0.0% 0.0%	\$38,825 \$408,274 \$65,773 \$39,826 \$160,231	\$14,365 \$151,061 \$24,336 \$14,736 \$59,285	\$53,190 \$559,335 \$90,109 \$54,562 \$219,516	\$0 \$0 \$0 \$0 \$0	\$53,190 \$559,335 \$90,109 \$54,562 \$219,516	12.0% 24.2% 39.8% 29.8% 22.4%	\$43,486 \$507,275 \$91,979 \$51,712 \$196,110	\$16,090 \$187,692 \$34,032 \$19,134 \$72,561	\$59,576 \$694,966 \$126,011 \$70,846 \$268,670
	CONSTRUCTION ESTIMATE TOTALS:	\$712,929	\$263,784	_	\$976,713	0.0%	\$712,929	\$263,784	\$976,713	\$0	\$976,713	24.9%	\$890,562	\$329,508	\$1,220,069
01	LANDS AND DAMAGES	\$2,362	\$591	25.0%	\$2,953	0.0%	\$2,362	\$591	\$2,953	\$0	\$2,953	16.2%	\$2,746	\$686	\$3,432
30 31	PLANNING, ENGINEERING & DESIGN CONSTRUCTION MANAGEMENT	\$92,752 \$71,293	\$9,275 \$7,129	10.0% 10.0%	\$102,027 \$78,422	0.0%	\$92,752 \$71,293	\$9,275 \$7,129	\$102,027 \$78,422	\$0 \$0	\$102,027 \$78,422	21.1% 39.7%	\$112,337 \$99,584	\$11,234 \$9,958	\$123,570 \$109,542
	PROJECT COST TOTALS:	\$879,336	\$280,779	31.9%	\$1,160,115		\$879,336	\$280,779	\$1,160,115	\$0	\$1,160,115	25.6%	\$1,105,227	\$351,386	\$1,456,613

Final General Re-evaluation Report & Final Supplemental, Environmental Impact Statement

CHIEF, COST ENGINEERING, John B. Petitbon PROJECT MANAGER, Jasmin M. Smith CHIEF, REAL ESTATE, Judith Y. Gutierrez CHIEF, RPEDS, Troy G. Constance CHIEF, ENGINEERING, Jean S. Vossen CHIEF, OPERATIONS, Michael F. Park **CHIEF, CONSTRUCTION, Stuart Waits** CHIEF, CONTRACTING, Deborah L. Logan CHIEF, PM-PB, Carol S. Burdine

CHIEF, DPM, Mark R. Wingate

#### \*\*\*\* CONTRACT COST SUMMARY \*\*\*\*

New Industrial Canal Lock and Connecting Channels PROJECT: LOCATION:

Orleans Parish, Louisiana

This Estimate reflects the scope and schedule in report; Final General Re-evaluation Report & Final Supplemental, Environmental Impact Statement

DISTRICT: New Orleans District

PREPARED: 6/13/2019

POC: CHIEF, COST ENGINEERING, John B. Petitbon

Civil	l Works Work Breakdown Structure		ESTIMATI	ED COST				FIRST COS Dollar Basi			TOTAL PROJE	CT COST (FULLY	FUNDED)	
			nate Prepared ive Price Leve		<b>13-Jun-19</b> 1-Oct-18	_	n Year (Bud ve Price Lew	• ,	2019 1 OCT 18					
WBS <u>UMBER</u> <i>A</i>	Civil Works <u>Feature &amp; Sub-Feature Description</u> <b>B</b>	COST (\$K) <b>C</b>	CNTG (\$K) <b>D</b>	CNTG (%) E	TOTAL _(\$K)_ <i>F</i>	ESC (%) <b>G</b>	COST (\$K) H	CNTG _(\$K) 	TOTAL _(\$K) 	Mid-Point <u>Date</u> <i>P</i>	INFLATED _(%)_ <i>L</i>	COST _(\$K) <b>M</b>	CNTG (\$K) N	FULL (\$K) <b>O</b>
02 05 08 09 11	RELOCATIONS LOCKS ROADS, RAILROADS & BRIDGES CHANNELS & CANALS LEVEES & FLOODWALLS	\$38,825 \$408,274 \$65,773 \$39,826 \$160,231	\$14,365 \$151,061 \$24,336 \$14,736 \$59,285	37.0% 37.0% 37.0% 37.0% 37.0%	\$53,190 \$559,335 \$90,109 \$54,562 \$219,516	0.0% 0.0% 0.0% 0.0% 0.0%	\$38,825 \$408,274 \$65,773 \$39,826 \$160,231	\$14,365 \$151,061 \$24,336 \$14,736 \$59,285	\$53,190 \$559,335 \$90,109 \$54,562 \$219,516	2023Q1 2026Q3 2030Q3 2028Q1 2026Q1	12.0% 24.2% 39.8% 29.8% 22.4%	\$43,486 \$507,275 \$91,979 \$51,712 \$196,110	\$16,090 \$187,692 \$34,032 \$19,134 \$72,561	\$59 \$694 \$126 \$70 \$268
01	CONSTRUCTION ESTIMATE TOTALS:	\$712,929 \$2,362	\$263,784 \$591	37.0%	<b>\$976,713</b> \$2,953	0.0%	\$712,929 \$2,362	\$263,784 \$591	\$976,713 \$2,953	2024Q2	16.2%	\$890,562 \$2,746	\$329,508 \$686	\$1,220 \$.
1.0% 0.5% 4.5% 0.5% 1.0% 0.5% 3.0% 1.0%	6 Planning & Environmental Compliance 6 Engineering & Design 6 Reviews, ATRs, IEPRs, VE 6 Life Cycle Updates (cost, schedule, risks) 6 Contracting & Reprographics 6 Engineering During Construction 6 Planning During Construction 6 Adaptive Management & Monitoring	\$7,129 \$3,565 \$32,082 \$3,565 \$7,129 \$3,565 \$21,388 \$7,129 \$71 \$7,129	\$713 \$356 \$3,208 \$356 \$713 \$356 \$2,139 \$713 \$7	10.0% 10.0% 10.0% 10.0% 10.0% 10.0% 10.0% 10.0%	\$7,842 \$3,921 \$35,290 \$3,921 \$7,842 \$3,921 \$23,527 \$7,842 \$78	0.0% 0.0% 0.0% 0.0% 0.0% 0.0% 0.0% 0.0%	\$7,129 \$3,565 \$32,082 \$3,565 \$7,129 \$3,565 \$21,388 \$7,129 \$7,129	\$713 \$356 \$3,208 \$356 \$713 \$356 \$2,139 \$713 \$7	\$7,842 \$3,921 \$35,290 \$3,921 \$7,842 \$3,921 \$23,527 \$7,842 \$78	2022Q2 2022Q2 2022Q2 2022Q2 2022Q2 2022Q2 2022Q2 2028Q1 2028Q1 2028Q1 2028Q1 2022Q2	12.8% 12.8% 12.8% 12.8% 12.8% 12.8% 39.7% 39.7% 39.7%	\$8,045 \$4,022 \$36,202 \$4,022 \$8,045 \$4,022 \$29,875 \$9,958 \$100 \$8,045	\$804 \$402 \$3,620 \$402 \$804 \$402 \$2,988 \$996 \$10 \$804	\$ \$3 \$ \$ \$ \$3
8.0% 1.0% 1.0%	6 Project Operation:	\$57,034 \$7,129 \$7,129	\$5,703 \$713 \$713	10.0% 10.0% 10.0%	\$62,738 \$7,842 \$7,842	0.0% 0.0% 0.0%	\$57,034 \$7,129 \$7,129	\$5,703 \$713 \$713	\$62,738 \$7,842 \$7,842	2028Q1 2028Q1 2028Q1	39.7% 39.7% 39.7%	\$79,667 \$9,958 \$9,958	\$7,967 \$996 \$996	\$8 \$1 \$1

# **Cost and Schedule Risk Analysis**

## **Cost:**


### **Contingency Analysis**


Contingency Analysis						
Most Likely Cost Estimate	\$879,821,000					
Confidence Level	Value	Contingency				
0%	959,004,890	9.00%				
5%	1,055,785,200	20.00%				
10%	1,073,381,620	22.00%				
15%	1,082,179,830	23.00%				
20%	1,090,978,040	24.00%				
25%	1,099,776,250	25.00%				
30%	1,117,372,670	27.00%				
35%	1,126,170,880	28.00%				
40%	1,126,170,880	28.00%				
45%	1,134,969,090	29.00%				
50%	1,143,767,300	30.00%				
55%	1,152,565,510	31.00%				
60%	1,161,363,720	32.00%				
65%	1,170,161,930	33.00%				
70%	1,178,960,140	34.00%				
75%	1,187,758,350	35.00%				
80%	1,205,354,770	37.00%				
85%	1,214,152,980	38.00%				
90%	1,231,749,400	40.00%				
95%	1,258,144,030	43.00%				
100%	1,381,318,970	57.00%				

## Schedule:

## **Contingency Analysis**

Base Case Schedule	126.0 Months					
Confidence Level	Value	Contingency				
0%	162.5 Months	29.00%				
5%	196.6 Months	56.00%				
10%	204.1 Months	62.00%				
15%	209.2 Months	66.00%				
20%	212.9 Months	69.00%				
25%	216.7 Months	72.00%				
30%	220.5 Months	75.00%				
35%	223.0 Months	77.00%				
40%	225.5 Months	79.00%				
45%	228.1 Months	81.00%				
50%	231.8 Months	84.00%				
55%	234.4 Months	86.00%				
60%	236.9 Months	88.00%				
65%	240.7 Months	91.00%				
70%	243.2 Months	93.00%				
75%	247.0 Months	96.00%				
80%	252.0 Months	100.00%				
85%	257.0 Months	104.00%				
90%	263.3 Months	109.00%				
95%	270.9 Months	115.00%				
100%	323.8 Months	157.00%				





## **MII Cost Estimate**

Print Date Sat 27 July 2019 Eff. Date 6/6/2019 U.S. Army Corps of Engineers
Project IHNCSD: Inner Harbor Navigation Canal Lock Replacement - Shallow Draft
New Report

Time 13:08:43

Title Page

Estimated by Darrell Normand, Eric Salamone, Miguel Ramos
Designed by MVN Structures Branch
Prepared by Darrell Normand, Eric Salamone, Miguel Ramos
Preparation Date 6/6/2019
Effective Date of Pricing 6/6/2019
Estimated Construction Time Days

New Section
IHNC Lock Replacement - Shallow Draft, 110' x 900' x 22' Lock
Lands and Damages
Relocations
Utility Relocations
Locks
Mobilization and Demobilization
Care and Diversion of Water
Temporary Cofferdam
Sheet Piling PS-31
Sand Fill
18" Thick Stone Cap
Jet Grout
Dewatering/Rewatering System
Temporary Protective Dolphins
36" Dia. Pipe w/ 9/16" wall
Structural steel W30x191
Structural steel C12x30
Miscellaneous Metals
Energy Absorption Fenders
Permanent Access Road and Parking and Landscaping
·

Roadway and Parking, Asphaltic2
Metal Guardrails2
Semi-Compacted Fill2
Purchase and Deliver Material2
Embankment Placement2
Testing2
Landscaping - 27 Acres2
Buildings, Project Operations:
Reservation Site Work
Office Building (1,350 SF)
Piles
Concrete2
Brick Facade
Metal Roof3
Interior Walls3
Doors3
Window and Shutters3
Insulation3
Finish3
Kitchen3
Bathroom3

Plumbing	
HVAC3	ļ
Kitchen Hood Venting3	ļ
Bathroom Venting3	ļ
Electrical Wiring	Į.
Specialty Systems4	ļ
Fire Protection4	ļ
Operation Maintenance Building (6,816 SF)4	ļ
Piles	Ļ
Concrete4	ļ
Brick Facade	ļ
Metal Roof4	ļ
Interior Walls	ļ
Doors	ļ
Window and Shutters	,
Insulation5	j
Finish5	j
Kitchen5	j
Fire Protection5	
Specialty Systems	,
Electrical Wiring5	j

Bathroom Venting	6
Kitchen Hood Venting	6
HVAC	6
Bathroom	6
Plumbing	6
Bridge Crane	6
Generation Building	6
Piles	6
Concrete	6
Brick Facade	6
Metal Roof	6
Doors	6
Louvers, Fans Etc	6
Fuel Tank	6
Electrical	6
Specialty Systems	7
Fire Protection System	7
Mechanical Building	7
Sector Gate North	7
Sector Gate South	7
Shops Buidling	7

Control House
Concrete
Brick Facade7
Metal Roof7
Doors
Finish8
Insulation8
Window and Shutters8
Hand Rail8
Stairs
Kitchen8
Kitchen Hood Venting8
Bathroom8
Bathroom Venting8
HVAC8
Electrical8
Special System8
Fire Protection System9
Fire Extinguishing System9
Elevator9
Ergo-compliant Storage Container Pad9

Piles	.9
Concrete	.9
Vater Supply and Distribution System	.9
Reservation Yard Potable Water Piping	.9
Public Water Service	.9
Fire Hydrants	.9
anitary Sewer and Distribution System	.9
Sanitary Sewer and Distribution System1	LO
Sanitary Treatment and Distribution System- WBV90	LO
thwork for Structures	10
ock Site-Backfill	LO
oundation Protection	LO
undation Work1	LO
heet Piling PZ-221	LO
Chamber Monoliths 24" PPC Piles	10
Satebay Monoliths 24" PPC Piles	10
torage Platform 24" PPC Piles	LO
ck Gates & Operating Machinery	10
letals1	10
Sector Gates1	10
Maintenance Bulkheads	10

Composite Timber Fenders 8"X 12" (On Gates)	
Machinery	
Gate Operating Machinery	
Concrete Floating Guidewall	
Cofferdam	
Sheetpile	
Bracing	
Guidewall	
HP 14X73	
Precast Concrete Pontoons	
Concrete, In Place	
Sand Fill	
Pontoon Timbers (12 x 12)	
Miscellaneous Metals	
Timber Guidewalls	
Guidewalls	
End Cells	
Sheet Piling PS-31	
Concrete Cap	
Sand Fill	
Lock Structure	

Concrete	12
Chamber Monoliths	12
Gatebay Monoliths	12
Storage Platform	12
Metals	12
Wall Armor	12
Floating Mooring Bits	12
Miscellaneous Metals	12
ılvert Valves & Oper. Mach.:	12
Metals	12
Culvert Roller Gates (4)	12
Culvert Maint. Bulkhead (4)	12
Culvert Invert Screens (4)	12
Mechanical	12
Culvert Valve Machinery	12
ping Systems	12
Mechanical	12
wer and Lighting Systems:	12
Electrical	12
Panelboards, etc	13
Lights	13

	Lightning Protection System	. 13
	Navigation	. 13
	Conduit and Wiring	
	Web Camera System	. 13
	Emergency Power	. 13
	Traffic Signals	. 13
Prog	gram Logic Control (PLC), Hardware Backup Controls	. 13
Ass	osciated General Items	. 13
De	emolition of Existing Lock, St Claude bridge	. 13
Tr	ee Removal	. 13
Si	te Work	. 14
	Permanent Mooring Facil. Cells	. 14
De	emolition of Coast Guard Facility	. 14
To	w Assistance Tugs	. 14
Roads	, Railroads & Bridges	. 14
St. C	Claude Bridge Replacement	. 14
Ва	ascule Bridges - Main and Temporary Channel	. 14
	Demolition (Ramps only)	. 14
	Structural Steel, Bascule Gate Leafs	
	Concrete, Gate Leaf Piers	. 14
	Piling, 18" Diameter Pipe Piles, Bridge Piers 1, 2, 3	. 14

Time 13:08:43

## New Report

Concrete, Approach Ramps, Bents	14
Concrete, Decking, Barriers, Girders	
Steel Sheet Piling, PZ-40 Retaining Wall Sheetpile	14
Temporary Retaining Structures (TRS) for Bridge Piers - Assume PZ-35 Sheetpile - Piers 1, 2, 3	14
Structural Excavation and Granular Backfill for Bridge Piers 1, 2, 3	15
Channels and Canals	15
Canals	15
Canals - Dredging (Excavation)	15
Canals - Dredging (Excavation)	15
Bank Stabilization	15
Site Work-North Bypass	15
Levees and Floodwalls	15
Associated General Items:	15
Floodwalls (West & East IHNC)	15
T-Wall Concrete	15
18" Dia. Steel Pipe Piles	15
Sheet Piling PZ-22	15
Pile Tests	15
Levee Setback	15
Compacted Embankment Fill For Floodwalls	16
Compacted Embankment Fill for Levee Access Roads	16

# U.S. Army Corps of Engineers Project IHNCSD: Inner Harbor Navigation Canal Lock Replacement - Shallow Draft New Report

Time 13:08:43

Table of Contents

Demolition of Existing Floodwall	. 16
Demolition of Concrete Floodwall	. 16
Extract Steel Sheet Piling	. 16
Extract 12" Concrete Piles	. 16

Print Date Sat 27 July 2019 Eff. Date 6/6/2019

## U.S. Army Corps of Engineers Project IHNCSD: Inner Harbor Navigation Canal Lock Replacement - Shallow Draft

New Report New Section Page 1

Time 13:08:43

Description	Quantity	UOM	ProjectCost
New Section			
IHNC Lock Replacement - Shallow Draft, 110' x 900' x 22' Lock			
Lands and Damages Lands and Damages	1.0000	) JOB	2,362,400.00
Relocations			
Utility Relocations  Cox Cable 5" pipe cable Entergy Gas 2-16" natural gas pipe lines  NOS&WB 20" water line  NOS&WB 2-30" reinforced concrete pipes  NOS&WB 20" C.I. pipe line Entergy power cables	2,500.0000 5,000.0000 2,500.0000 5,000.0000 2,500.0000 5,000.0000	) LF ) LF ) LF ) LF	1,275,000.00 10,000,000.00 5,000,000.00 15,000,000.00 5,000,000.00 2,550,000.00
Locks			
Mobilization and Demobilization Mobilization and Demobilization	1.0000	) EA	24,486,465.29
Care and Diversion of Water			
Temporary Cofferdam			
Sheet Piling PS-31 Remove Piles Unloading Piling Driving Sheetpile - PS-31 PS 31 Material Price (includes delivery) PS-31 splicing	940,310.0000 11,900.0000 940,310.0000 940,310.0000 5,950.0000	EA SF LB	1,281,540.34 596,219.08 3,076,518.23 1,376,799.29 3,100,644.35
Sand Fill  Excavation, bulk, dragline, bank measure, unclassified soil, 3 C.Y. bucket, excavate  Granular Fill	72,975.0000 72,975.0000		117,986.91 1,444,147.10
18" Thick Stone Cap Rip-rap and rock lining, random, broken stone, machine placed for slope protection	8,515.5000	) TON	323,554.25
Jet Grout Grout for riprap	297,230.0000	) CY	63,035,730.49
Dewatering/Rewatering System  Dewatering/Rewatering System  Well Point System  Wells and piezometers	1.0000 1.0000 1.0000	) EA	2,297,503.89 24,742,349.55 3,534,621.36
Temporary Protective Dolphins			
36" Dia. Pipe w/ 9/16" wall Pile Unloading Pile Installation Paint Piles, Coal-Tar Epoxy 36" Pipe Pile, 9/16" thk (includes delivery)	80.0000 12,000.0000 15,072.0000 2,835,600.0000	VLF SFC	7,245.87 170,807.73 64,485.53 4,044,036.66
Structural steel W30x191			

Print Date Sat 27 July 2019

U.S. Army Corps of Engineers

Eff. Date 6/6/2019

U.S. Army Corps of Engineers

Time 13:08:43

Project IHNCSD: Inner Harbor Navigation Canal Lock Replacement - Shallow Draft

New Section Page 2

New Report

Description Structural steel member, 100-ton project, 1 to 2 story building, W30x191, A992 steel, shop fabricated, incl shop primer, bolted connections	Quantity UOM 462.0000 LF	ProjectCost 247.341.78
Structural steel C12x30	402.0000 EF	247,341.70
Structural steel member, channels, C & MC, 11 to 20 plf, A992 steel, shop fabricated, incl shop primer, bolted connections	5.4600 TON	36,560.42
Miscellaneous Metals Steel Plates installation (Corner Protection, Vertical Seals, Walkways)	32,750.0000 LB	329,204.57
Energy Absorption Fenders Jetties, dock accessories, fender, vinyl, corner piece	200.0000 EA	7,174.18
Permanent Access Road and Parking and Landscaping		
Roadway and Parking, Asphaltic Asphalt Paving, plant mixed asphaltic base courses for roadways and large paved areas, bituminous concrete, 6" thick	5,000.0000 SY	226,470.98
Metal Guardrails Guard rail transitions, double thrie beam, includes delivery and installation	900.0000 LF	95,434.78
Semi-Compacted Fill		
Purchase and Deliver Material Hauling Operation to NOV-06 from Plaquemines Dirt and Clay	11,721.0000 LCY	388,579.75
Embankment Placement Placing Compacted Fill	7,814.0000 ECY	53,771.05
Testing Testing- Atterberg Testing- In-place Density, Organic, Moisture Control Testing- Compaction Curves Testing- Sand Content Settlement Gages	10.0000 EA 44.0000 EA 2.0000 EA 44.0000 EA 4.0000 EA	883,66 8,942,59 441,83 3,499,28 5,655,39
Landscaping - 27 Acres 39 Hydro or air seeding with mulch and fertilizer, installed price watering, turf establishment Fert & seed Mob/Demob	27.0000 ACR 40.2800 DAY 5.0350 EA	71,576.08 64,068.55 8,898.41
Buildings, Project Operations:		
Reservation Site Work Special Systems Intercom	1.0000 LS 1.0000 LS	88,365.53 26,509.66
Office Building (1,350 SF)		
Piles Piling special costs, cutoffs, concrete piles, plain Prestressed concrete piles, square, 40' long, 12" square, priced using 200 piles, excludes pile caps or mobilization	19.0000 EA 1,672.0000 VLF	2,399.43 78,960.53
Concrete Structural concrete, in place, elevated slab, flat plate, 125 psf superimposed load, 25' span, includes forms(4 uses), reinforcing steel, and finishing	40.0000 CY	34,417.61
Brick Facade Brick veneer masonry, standard brick, select common, running bond, T.L. lots, 6.75/S.F., 4" x 2-2/3" x 8", includes 3% brick and 25% mortar waste, excludes scaffolding, grout and reinforcing Scaffolding, steel tubular, regular, labor only to erect & dismantle, bldg ext, wall face, 6'-4" x 5' frames, 13 to 20 stories, excl. planks Scaffolding, steel tubular, regular, rent/month only for complete system for interior spaces, 6'-4" x 5' frames, excl. planks	1,650.0000 SF 13.0000 CSF 13.0000 CCF	28,807.54 4,958.10 326.96

Print Date Sat 27 July 2019

U.S. Army Corps of Engineers

Eff. Date 6/6/2019

U.S. Army Corps of Engineers

Project IHNCSD: Inner Harbor Navigation Canal Lock Replacement - Shallow Draft

Time 13:08:43

New Report New Section Page 3

Description	Quantity	MOU	ProjectCost
Metal Roof  Roof truss, using galv LB metal studs, fink (W) or King Post type, to 4:12 pitch, 18 ga x 4" chords, 28' span, excl erection, bridging & bracing, fabrication only of trusses on-site  Steel roofing panels, on steel frame, flat profile, 1-3/4" standing seams, standard finish, 12" wide, 24 gauge	30.0000 2,300.0000		10,551.86 25,674.89
Interior Walls Partition Wall, interior, standard, taped both sides, installed on & incl.25 ga, NLB metal studs, 6" wide, 16" O.C., 8' to 12' high, 1/2" gypsum drywall	3,000.0000	SF	19,883.61
Doors Doors, commercial, steel, insulated, half glass, 18 ga., 3'-0" x 7'-0" x 1-3/4" thick Door frames, steel channels with anchors and bar stops, 6" channel@ 8.2 lb/LF, 3' x 7' door, weighs 150 lb Door hardware, lockset, heavy duty, cylindrical, with sectional trim, keyed, single cylinder function Door hardware, hinges, full mortise, high frequency, steel base, US26, 4-1/2" x 4-1/2" Door hardware, lockset, heavy duty, cylindrical, with sectional trim, residential, interior door, minimum Doors, commercial, steel, flush, half glass, hollow core, hollow metal, 20 ga., 3'-0" x 7'-0"	4.0000 12.0000 4.0000 18.0000 8.0000	EA EA PR EA	5,686.99 7,860.95 1,709.49 2,437.69 687.79 10,404.48
Window and Shutters Windows, aluminum, commercial grade, stock units, projected, with screen, enamel finish, insulating glass, 4'-5" x 5'-3", incl. frame and glazing Exterior Shutters, metal, louvered	8.0000 8.0000		7,447.90 6,111.87
Insulation Wall Insulation, Rigid, fiberglass, foil faced, 1" thick, R4.3, 6#/CF Blanket insulation, for walls or ceilings, foil faced fiberglass, 12" thick, R38, 15" wide	1,804.0000 1,425.0000		8,256.57 4,031.11
Finish Paints & Coatings, walls & ceilings, interior, concrete, drywall or plaster, oil base, 3 coats, smooth finish, roller Moldings, exterior, trim, built-up, pine, three piece, maximum	3,500.0000 800.0000		5,260.27 15,761.04
Kitchen  Custom Cabinets, kitchen base cabinets, hardwood, prefinished, range or sink base, 2 doors below, 24" deep, 35" high, 42" wide, excl. countertops  Custom Cabinets, kitchen wall cabinets, hardwood, prefinished, 2 doors, 12" deep, 12" high, 30" wide  Custom Cabinets, kitchen base cabinets, hardwood, prefinished, 2 top drawers, 2 doors below, 24" deep, 35" high, 48" wide, excl. countertops  Microwave ovens, residential appliances, 1.5 C.F., maximum  Sink, kitchen, counter top style, stainless steel, self rimming, double bowl, 43" x 22", includes faucet and drain  Faucets/fittings, kitchen sink, single control lever handle, polished brass, with pull out spray  Refrigerator, residential appliances, no frost, 6 C.F.  Misc Plumbing	2.0000 2.0000 1.0000 1.0000 1.0000 1.0000 1.0000	EA EA EA EA EA	1,804.14 1,060.02 1,108.55 1,415.48 2,473.55 655.22 478.15 2,860.00
Bathroom Water closet, tank type, vitreous china, floor mounted, combination, one piece, includes seat, supply pipe with stop Faucets/fittings, Bathroom sink, single control lever handle	2.0000 2.0000		9,164.50 6,224.51
Plumbing Plumbing, Piping, sewage vent, cast iron, B & S, 4" diameter, excludes excavation or backfill	500.0000	LF	27,439.72
HVAC Rooftop air conditioner, single zone, electric cool, gas heat SEER 13, 4 ton cooling, 95 MBH heating, 4 ton cooling, 95 MBH heating SHEER 13, includes, standard controls, curb and economizer	4.0000	EA	60,486.64
Kitchen Hood Venting Range hood, residential appliances, vented, custom, 2 speed, 42" wide	1.0000	EA	3,415.26
Bathroom Venting Bathroom vent fan, resi, hook-up, (use w/above hook-up), custom model, 50 CFM	2.0000	EA	649.82
Electrical Wiring Rigid galvanized steel conduit, 3/4" diameter, to 15' H, incl 2 terminations, 2 elbows, 11 beam clamps, and 11 couplings per 100 LF	1,330.0000	LF	21,513.54

New Report

New Section Page 4

Description	Quantity UOM	ProjectCost
Wire, copper, stranded, 600 volt, #12, type THWN-THHN, in raceway Rigid galvanized steel conduit, 3" diameter, to 15' H, incl 2 terminations, 2 elbows, 11 beam clamps, and 11 couplings per 100 LF	53.2000 CLF 20.0000 LF	5,310.64 1,264.54
Wire, copper, stranded, 600 volt, 250 kcmil, type THWN-THHN, in raceway	1.2000 CLF	1,594.10
Wire, copper, stranded, 600 volt, 1/0, type THWN-THHN, in raceway	0.3000 CLF	201.01
Terminal lugs, solderless, 250 kcmil Terminal lugs, solderless, 1/0 to 2/0	8.0000 EA 2.0000 EA	815.08 113.54
	2.0000 LA	115.54
Specialty Systems Detection Systems, ultrasonic motion detector, 12 volt, excl. wires & conduit	3.0000 EA	2,337.43
Detection Systems, door switches, hinge switch, excl. wires & conduit	4.0000 EA	1,130.90
Intrusion Detection Systems, misc. equipment, switch, electric strike	4.0000 EA	2,640.06
Detection Systems, siren, excl. wires & conduit Access Control Panel	1.0000 EA 1.0000 EA	496.86 7.064.47
Alam control panel	1.0000 EA	2,776.20
Intercom w/ manual release	1.0000 EA	258.01
Access Control Equipment, entrance card reader, proximity	4.0000 EA	4,654.35
Fiber optics, rack housing, 4 rack spaces, 12 panels (144 fibers) Workstation	1.0000 EA 1.0000 EA	1,492.86 9.507.65
Ethernet switch	1.0000 EA	132.55
Alarm Keypad	1.0000 EA	441.83
Rigid galvanized steel conduit, 3/4" diameter, to 15' H, incl 2 terminations, 2 elbows, 11 beam clamps, and 11 couplings per 100 LF Low voltage switching, control wire, 2 conductor	650.0000 LF 7.0000 CLF	10,514.14 1,413.32
ASSAULT STREAM TO REPORT TO ANALYZE AND ANALYZE ANALYZE AND ANALYZE AND ANALYZE ANALYZE ANALYZE ANALYZE ANALYZE AN	7.0000 CEI	1,415.52
Fire Protection Fire Alarm, pull station, manual, standard	4.0000 EA	880.28
Fire Alarm & Detection, detectors, photoelectric smoke, releasing unit, single stage, 120V	2.0000 EA	522.52
Detection Systems, strobe & horn, ADA type, excl. wires & conduit	2.0000 EA	911.76
Detection Systems, strobe, excl. wires & conduit Fire Alarm & Detection, control panel, 4 zone	2.0000 EA 1.0000 EA	578.50 2,144.77
Rigid galvanized steel conduit, 3/4" diameter, to 15' H, incl 2 terminations, 2 elbows, 11 beam clamps, and 11 couplings per 100 LF	300.0000 LF	4.852.68
Low voltage switching, control wire, 2 conductor	3.5000 CLF	706.66
Operation Maintenance Building (6,816 SF)		
Piles		
Piling special costs, cutoffs, concrete piles, plain	64.0000 EA 5.632.0000 VLF	8,082.29
Prestressed concrete piles, square, 40' long, 12" square, priced using 200 piles, excludes pile caps or mobilization	5,632.0000 VLF	265,972.33
Concrete Structural concrete, in place, elevated slab, flat plate, 125 psf superimposed load, 25' span, includes forms(4 uses), reinforcing steel, and finishing	230.0000 CY	197,901.24
Brick Facade		
Brick veneer masonry, standard brick, select common, running bond, T.L. lots, 6.75/S.F., 4" x 2-2/3" x 8", includes 3% brick and 25% mortar waste, excludes scaffolding, grout and reinforcing	6,000.0000 SF	104,754.70
Scaffolding, steel tubular, regular, rent/month only for complete system for interior spaces, 6' -4" x 5' frames, excl. planks Scaffolding, steel tubular, regular, labor only to erect & dismantle, bldg ext, wall face, 6'-4" x 5' frames, 13 to 20 stories, excl. planks	29.0000 CCF 29.0000 CSF	729.37 11,060.38
	29.0000 CSF	11,060.38
Metal Roof Steel roofing panels, on steel frame, flat profile, 1-3/4" standing seams, standard finish, 12" wide, 24 gauge	6.500.0000 SF	72.559.47
Roof Deck Insulation, extruded polystyrene, 2" thick, R10, 25 PSI compressive strength	6,500.0000 SF	18,351.15
Interior Walls	626	116
Partition Wall, interior, standard, taped both sides, installed on & incl.25 ga, NLB metal studs, 6" wide, 16" O.C., 8' to 12' high, 1/2" gypsum drywall	4,800.0000 SF	31,813.77
Doors		

U.S. Army Corps of Engineers

Time 13:08:43

Project IHNCSD: Inner Harbor Navigation Canal Lock Replacement - Shallow Draft

New Section Page 5

#### Harbor Navigation Canal Lock Replacement - Shallow New Report

Description	Quantity UOM	ProjectCost
Doors, commercial, steel, insulated, half glass, 18 ga., 3'-0" x 7'-0" x 1-3/4" thick	8.0000 EA	11,373.98
Door frames, steel channels with anchors and bar stops, 6" channel@ 8.2 lb/LF, 3' x 7' door, weighs 150 lb	10.0000 EA 8.0000 EA	6,550.80
Door hardware, lockset, heavy duty, cylindrical, with sectional trim, keyed, single cylinder function Door hardware, hinges, full mortise, high frequency, steel base, US26, 4-1/2" x 4-1/2"	18.0000 EA	3,418.98 2.437.69
Door hardware, lockset, heavy duty, cylindrical, with sectional trim, residential, interior door, minimum	2.0000 EA	171.95
Doors, commercial, steel, flush, half glass, hollow core, hollow metal, 20 ga., 3'-0" x 7'-0"	2.0000 EA	2,601.12
Doors, overhead, commercial, stock, fiberglass and aluminum, heavy duty, sectional, 12' x 12' high, excl. frames	2.0000 EA	13,653.71
Doors, overhead, commercial, stock, steel, heavy duty, sectional, manual, 24 gauge, 10' x 10' high	2.0000 EA	6,283.45
Window and Shutters Windows, aluminum, commercial grade, stock units, projected, with screen, enamel finish, insulating glass, 4'-5" x 5'-3", incl. frame and glazing	2.0000 EA	1,861.97
windows, authinium, commercial grade, stock units, projected, with screen, enamer mish, insulating glass, 4-5 x 5-5, incl. frame and grazing  Exterior Shutters, metal, louvered	2.0000 EA 2.0000 PR	1,527.97
Insulation		
Wall Insulation, Rigid, fiberglass, foil faced, 1" thick, R4.3, 6#/CF	8,416.0000 SF	38,518.47
Blanket insulation, for walls or ceilings, foil faced fiberglass, 12" thick, R38, 15" wide	3,766.0000 SF	10,653.46
Finish	et de trouver de de trouver et de tre	providence and
Paints & Coatings, walls & ceilings, interior, concrete, drywall or plaster, oil base, 3 coats, smooth finish, roller	4,650.0000 SF 800.0000 LF	6,988.64
Moldings, exterior, trim, built-up, pine, three piece, maximum	800.0000 LF	15,761.04
Kitchen Custom Cabinets, kitchen base cabinets, hardwood, prefinished, range or sink base, 2 doors below, 24" deep, 35" high, 42" wide, excl. countertops	4.0000 EA	3.608.28
Unit kitchen, combination range, refrigerator and sink, average, 72" wide	1.0000 EA	12,945.51
Fire Protection		
Fire Alarm, pull station, manual, standard	6.0000 EA	1,320.42
Detection Systems, strobe & horn, ADA type, excl. wires & conduit	7.0000 EA	3,191.15
Fire Alarm & Detection, control panel, 8 zone Rigid galvanized steel conduit, 3/4" diameter, to 15' H, incl 2 terminations, 2 elbows, 11 beam clamps, and 11 couplings per 100 LF	1.0000 EA 390.0000 LF	4,687.70 6,308.48
Low voltage switching, control wire, 2 conductor	4.5000 CLF	908.57
Specialty Systems		
Detection Systems, ultrasonic motion detector, 12 volt, excl. wires & conduit	4.0000 EA	3,116.58
Detection Systems, door switches, hinge switch, excl. wires & conduit	7.0000 EA	1,979.08
Intrusion Detection Systems, misc. equipment, switch, electric strike  Detection Systems, siren, excl. wires & conduit	4.0000 EA 1.0000 EA	2,640.06 496.86
Access Control Panel	1.0000 EA 1.0000 EA	7.064.47
Alarm control panel	1.0000 EA	2,776.20
Access Control Equipment, entrance card reader, proximity	4.0000 EA	4,654.35
Ethernet switch	1.0000 EA	132.55
Rigid galvanized steel conduit, 3/4" diameter, to 15' H, incl 2 terminations, 2 elbows, 11 beam clamps, and 11 couplings per 100 LF Low voltage switching, control wire, 2 conductor	710.0000 LF 7.5000 CLF	11,484.67 1,514.28
Electrical Wiring	7.5000 021	1,514.20
Rigid galvanized steel conduit, 3/4" diameter, to 15' H, incl 2 terminations, 2 elbows, 11 beam clamps, and 11 couplings per 100 LF	3,040,0000 LF	49.173.82
Wire, copper, stranded, 600 volt, #12, type THWN-THHN, in raceway	121.6000 CLF	12,138.61
Kitchen wiring	1.0000 LS	17,673.11
Rigid galvanized steel conduit, 4" diameter, to 15" H, incl 2 terminations, 2 elbows, 11 beam clamps, and 11 couplings per 100 LF	20.0000 LF 1.2000 MLF	1,689.50
Wire, copper, stranded, 600 volt, 600 kcmil, type THWN-THHN, in raceway Wire, copper, stranded, 600 volt, 3/0, type THWN-THHN, in raceway	1.2000 MLF 0.3000 CLF	10,594.15 279.93
Terminal luas, solderless, 600 kcmil	8.0000 EA	1,326.82
Terminal lugs, solderless, 3/0	2.0000 EA	156.67

Print Date Sat 27 July 2019 Eff. Date 6/6/2019

#### U.S. Army Corps of Engineers Project IHNCSD: Inner Harbor Navigation Canal Lock Replacement - Shallow Draft

New Report

New Section Page 6

Time 13:08:43

Description	Quantity	UOM	ProjectCost
Bathroom Venting Bathroom vent fan, resi, hook-up, (use w/above hook-up), custom model, 50 CFM	2.0000	EA	649.82
Kitchen Hood Venting Range hood, residential appliances, vented, custom, 2 speed, 42" wide	1.0000	EA	3,415.26
HVAC Rooftop air conditioner, single zone, electric cool, gas heat, 12.5 ton cooling, 230 MBH heating, includes, standard controls, curb and economizer	1.0000	EA	23,513.80
Bathroom Water closet, tank type, vitreous china, floor mounted, combination, one piece, includes seat, supply pipe with stop Faucets/fittings, Bathroom sink, single control lever handle Lavatory, wall hung, vitreous china, white, with backsplash, wheelchair type, single bowl, 27" x 20", includes trim Lavatory, wall hung, vitreous china, white, with backsplash, single bowl, for wall carrier, add Faucets/fittings, lavatory faucet, center set with pop-up drain	3.0000 4.0000 2.0000 3.0000 8.0000	EA EA EA	13,746.75 12,449.01 3,502.85 2,364.83 2,294.79
Plumbing Plumbing, Piping, sewage vent, cast iron, B & S, 4" diameter, excludes excavation or backfill	500.0000	LF	27,439.72
Bridge Crane Overhead Bridge Cranes, under hung hoist, electric operating, 1 girder, 5 ton, 30' span Crane Rail, box beam bridge, running track only, 105 lb per yard, 20' piece, excl. equipment	1.0000 162.0000		60,395.64 9,744.91
Generation Building			
Piles Piling special costs, cutoffs, concrete piles, plain Prestressed concrete piles, square, 40' long, 12" square, priced using 200 piles, excludes pile caps or mobilization	28.0000 2,464.0000		3,536.00 116,362.89
Concrete Structural concrete, in place, elevated slab, flat plate, 125 psf superimposed load, 25' span, includes forms(4 uses), reinforcing steel, and finishing	35.0000	CY	30,115.41
Brick Facade Brick veneer masonry, standard brick, select common, running bond, T.L. lots, 6.75/S.F., 4" x 2-2/3" x 8", includes 3% brick and 25% mortar waste, excludes scaffolding, grout and reinforcing Scaffolding, steel tubular, regular, rent/month only for complete system for interior spaces, 6' -4" x 5' frames, excl. planks Scaffolding, steel tubular, regular, labor only to erect & dismantle, bldg ext, wall face, 6'-4" x 5' frames, 13 to 20 stories, excl. planks	1,400.0000 39.5000 39.5000	CCF	24,442.76 993.46 15,065.00
Metal Roof Steel roofing panels, on steel frame, flat profile, 1-3/4" standing seams, standard finish, 12" wide, 24 gauge Roof Deck Insulation, extruded polystyrene, 2" thick, R10, 25 PSI compressive strength Roof truss, using galv LB metal studs, fink (W) or King Post type, to 4:12 pitch, 18 ga x 4" chords, 32' span, excl erection, bridging & bracing, fabrication only of trusses on-site	1,800.0000 1,800.0000 29.0000	SF	20,093.39 5,081.86 11,041.71
Doors Doors, commercial, steel, insulated, half glass, 18 ga., 3'-0" x 7'-0" x 1-3/4" thick Door frames, steel channels with anchors and bar stops, 6" channel@ 8.2 lb/LF, 3' x 7' door, weighs 150 lb Door hardware, lockset, heavy duty, cylindrical, with sectional trim, keyed, single cylinder function Door hardware, hinges, full mortise, high frequency, steel base, US26, 4-1/2" x 4-1/2"	8.0000 2.0000 2.0000 3.0000	EA EA	11,373.98 1,310.16 854.74 406.28
Louvers, Fans Etc Louvers, aluminum, 24" x 30" Fans, centrifugal, backward inclined, V-belt driven, 230 V, 3 phase, 1/2" S.P., 1-1/2 H.P., 8350 CFM, 30" diameter wheel	1.0000 2.0000		572.14 13,966.92
Fuel Tank Storage Tanks, steel, above ground, double wall, 3,000 gallons	1.0000	EA	21,825.76
Electrical			

Print Date Sat 27 July 2019 Eff. Date 6/6/2019 U.S. Army Corps of Engineers
Project IHNCSD: Inner Harbor Navigation Canal Lock Replacement - Shallow Draft Time 13:08:43

New Report

New Section Page 7

Description	Quantity UOM	ProjectCost
Rigid galvanized steel conduit, 3/4" diameter, to 15' H, incl 2 terminations, 2 elbows, 11 beam clamps, and 11 couplings per 100 LF Wire, copper, stranded, 600 volt, #12, type THWN-THHN, in raceway	180.0000 LF 7.2000 CLF	2,911.61 718.73
Specialty Systems	7.2000 021	710.70
Detection Systems, ultrasonic motion detector, 12 volt, excl. wires & conduit Detection Systems, door switches, hinge switch, excl. wires & conduit	4.0000 EA 7.0000 EA	3,116.58 1.979.08
Intrusion Detection Systems, misc. equipment, switch, electric strike	4.0000 EA	2,640.06
Detection Systems, siren, excl. wires & conduit Access Control Panel	1.0000 EA 1.0000 EA	496.86 7,064.47
Alarm control panel	1.0000 EA	2,776.20
Access Control Equipment, entrance card reader, proximity Ethernet switch	4.0000 EA 1.0000 EA	4,654.35 132.55
Rigid galvanized steel conduit, 3/4" diameter, to 15' H, incl 2 terminations, 2 elbows, 11 beam clamps, and 11 couplings per 100 LF	710.0000 LF	11,484.67
Low voltage switching, control wire, 2 conductor	7.5000 CLF	1,514.28
Fire Protection System Fire Alarm, pull station, manual, standard	1.0000 EA	220.07
Detection Systems, strobe & horn, ADA type, excl. wires & conduit	1.0000 EA 100.0000 LF	455.88 1,617.56
Rigid galvanized steel conduit, 3/4" diameter, to 15' H, incl 2 terminations, 2 elbows, 11 beam clamps, and 11 couplings per 100 LF Low voltage switching, control wire, 2 conductor	1.0000 CLF	201.90
Mechanical Building		
Sector Gate North		000:07
Fire Alarm, pull station, manual, standard Detection Systems, strobe & horn, ADA type, excl. wires & conduit	1.0000 EA 1.0000 EA	220.07 455.88
Rigid galvanized steel conduit, 3/4" diameter, to 15' H, incl 2 terminations, 2 elbows, 11 beam clamps, and 11 couplings per 100 LF	100.0000 LF	1,617.56
Low voltage switching, control wire, 2 conductor  Sector Gate South	1.0000 CLF	201.90
Fire Alarm, pull station, manual, standard	1.0000 EA	220.07
Detection Systems, strobe & horn, ADA type, excl. wires & conduit Rigid galvanized steel conduit, 3/4" diameter, to 15' H, incl 2 terminations, 2 elbows, 11 beam clamps, and 11 couplings per 100 LF	1.0000 EA 100.0000 LF	455.88 1.617.56
Low voltage switching, control wire, 2 conductor	1.0000 CLF	201.90
Shops Buidling	4 0000 54	200.07
Fire Alarm, pull station, manual, standard Detection Systems, strobe & horn, ADA type, excl. wires & conduit	1.0000 EA 1.0000 EA	220.07 455.88
Rigid galvanized steel conduit, 3/4" diameter, to 15' H, incl 2 terminations, 2 elbows, 11 beam clamps, and 11 couplings per 100 LF	100.0000 LF	1,617.56
Low voltage switching, control wire, 2 conductor  Control House	1.0000 CLF	201.90
Concrete		
Structural concrete, in place, elevated slab, flat plate, 125 psf superimposed load, 25' span, includes forms(4 uses), reinforcing steel, and finishing	40.0000 CY	34,417.61
Brick Facade Scaffolding, steel tubular, regular, rent/month only for complete system for interior spaces, 6'-4" x 5' frames, excl. planks	20.0000 CCF	503.02
Scaffolding, steel tubular, regular, labor only to erect & dismantle, bldg ext, wall face, 6'-4" x 5' frames, 13 to 20 stories, excl. planks	20.0000 CSF	7,627.85
Brick veneer masonry, standard brick, select common, running bond, T.L. lots, 6.75/S.F., 4" x 2-2/3" x 8", includes 3% brick and 25% mortar waste, excludes scaffolding, grout and reinforcing	2,002.0000 SF	34,953.15
Metal Roof Steel roofing panels, on steel frame, flat profile, 1-3/4" standing seams, standard finish, 12" wide, 24 gauge	1,800,0000 SF	20.093.39
Roof Deck Insulation, extruded polystyrene, 2" thick, R10, 25 PSI compressive strength	1,800.0000 SF	5,081.86

Print Date Sat 27 July 2019 Eff. Date 6/6/2019

## U.S. Army Corps of Engineers Project IHNCSD: Inner Harbor Navigation Canal Lock Replacement - Shallow Draft

New Report

Description

Roof truss, using galv LB metal studs, fink (W) or King Post type, to 4:12 pitch, 18 ga x 4" chords, 32' span, excl erection, bridging & bracing, fabrication only of trusses on-site

New Section Page 8

Quantity UOM ProjectCost 29.0000 EA 11,041.71

Time 13:08:43

		,
<b>Doors</b> Doors, commercial, steel, insulated, half glass, 18 ga., 3'-0" x 7'-0" x 1-3/4" thick Door frames, steel channels with anchors and bar stops, 6" channel@ 8.2 lb/LF, 3' x 7' door, weighs 150 lb Door hardware, lockset, heavy duty, cylindrical, with sectional trim, keyed, single cylinder function Door hardware, hinges, full mortise, high frequency, steel base, US26, 4-1/2" x 4-1/2"	5.0000 EA 5.0000 EA 5.0000 EA 7.5000 PR	7,108.74 3,275.40 2,136.86 1,015.70
Finish Paints & Coatings, walls & ceilings, interior, concrete, drywall or plaster, oil base, 3 coats, smooth finish, roller Moldings, exterior, trim, built-up, pine, three piece, maximum	1,932.0000 SF 800.0000 LF	2,903.67 15,761.04
Insulation Wall Insulation, Rigid, fiberglass, foil faced, 1" thick, R4.3, 6#/CF Blanket insulation, for walls or ceilings, foil faced fiberglass, 12" thick, R38, 15" wide	1,932.0000 SF 1,105.0000 SF	8,842.40 3,125.88
Window and Shutters Windows, aluminum, commercial grade, stock units, projected, with screen, enamel finish, insulating glass, 4'-5" x 5'-3", incl. frame and glazing Exterior Shutters, metal, louvered	7.0000 EA 7.0000 PR	6,516.91 5,347.89
Hand Rail Railing, pipe, aluminum, dark anodized finish, 3 rails, 1-1/2" dia, shop fabricated	522.0000 LF	106,999.98
Stairs Stair, shop fabricated, steel, 4'-0" W, incl picket railing, stringers, metal pan treads, excl concrete for pan treads, per riser	42.0000 RSR	49,010.55
Kitchen Custom Cabinets, kitchen base cabinets, hardwood, prefinished, range or sink base, 2 doors below, 24" deep, 35" high, 42" wide, excl. countertops Unit kitchen, combination range, refrigerator and sink, average, 72" wide	4.0000 EA 1.0000 EA	3,608.28 12,945.51
Kitchen Hood Venting Range hood, residential appliances, vented, custom, 2 speed, 42" wide	1.0000 EA	3,415.26
Bathroom Water closet, tank type, vitreous china, floor mounted, combination, one piece, includes seat, supply pipe with stop Faucets/fittings, Bathroom sink, single control lever handle Lavatory, wall hung, vitreous china, white, with backsplash, wheelchair type, single bowl, 27" x 20", includes trim Faucets/fittings, lavatory faucet, center set with pop-up drain	3.0000 EA 3.0000 EA 3.0000 EA 3.0000 EA	13,746.75 9,336.76 5,254.28 860.55
Bathroom Venting Bathroom vent fan, resi, hook-up, (use w/above hook-up), custom model, 50 CFM	3.0000 EA	974.72
HVAC Rooftop air conditioner, single zone, electric cool, gas heat, 2 ton cooling, 55 MBH heating, includes, standard controls, curb and economizer	1.0000 EA	7,704.73
Electrical Rigid galvanized steel conduit, 3/4" diameter, to 15' H, incl 2 terminations, 2 elbows, 11 beam clamps, and 11 couplings per 100 LF Wire, copper, stranded, 600 volt, #12, type THWN-THHN, in raceway Rigid galvanized steel conduit, 2" diameter, to 15' H, incl 2 terminations, 2 elbows, 11 beam clamps, and 11 couplings per 100 LF Wire, copper, stranded, 600 volt, 1/0, type THWN-THHN, in raceway Wire, copper, stranded, 600 volt, #2, type THWN-THHN, in raceway Terminal lugs, solderless, 1/0 to 2/0 Terminal lugs, solderless, #2 to #1	1,150,0000 LF 46,0000 CLF 20,0000 LF 1,2000 CLF 0,3000 CLF 8,0000 EA 2,0000 EA	18,601.94 4,591.91 682.96 804.03 130.30 454.18 81.95
Special System Detection Systems, ultrasonic motion detector, 12 volt, excl. wires & conduit	1.0000 EA	779.14

Print Date Sat 27 July 2019
U.S. Army Corps of Engineers

Eff. Date 6/6/2019
Project IHNCSD: Inner Harbor Navigation Canal Lock Replacement - Shallow Draft

New Report

New Section Page 9

Time 13:08:43

Description	Quantity UOM	
Detection Systems, door switches, hinge switch, excl. wires & conduit	2.0000 EA 2.0000 EA	565.45 1.320.03
Intrusion Detection Systems, misc. equipment, switch, electric strike Detection Systems, siren, excl. wires & conduit	1.0000 EA	496.86
Access Control Panel	1.0000 EA	7,064.47
Alarm control panel	1.0000 EA	2,776.20
Access Control Equipment, entrance card reader, proximity	2.0000 EA	2,327.17
Ethernet switch Rigid galvanized steel conduit, 3/4" diameter, to 15' H, incl 2 terminations, 2 elbows, 11 beam clamps, and 11 couplings per 100 LF	1.0000 EA 330.0000 LF	132.55 5.337.95
Low voltage switching, control wire, 2 conductor	4.0000 CLF	807.61
Fire Protection System		
Fire Alarm, pull station, manual, standard Detection Systems, strobe & horn, ADA type, excl. wires & conduit	2.0000 EA 4.0000 EA	440.14 1.823.52
Detection Systems, strobe, excl. wires & conduit  Detection Systems, strobe, excl. wires & conduit	3.0000 EA	867.75
Fire Alarm & Detection, control panel, 4 zone	1.0000 EA	2,144.77
Rigid galvanized steel conduit, 3/4" diameter, to 15' H, incl 2 terminations, 2 elbows, 11 beam clamps, and 11 couplings per 100 LF	330.0000 LF	5,337.95
Low voltage switching, control wire, 2 conductor	4.0000 CLF	807.61
Automatic Extinguishing System	1.0000 LS	17,673.11
Fire Extinguishing System Sprinkler Systems, preaction, water & detector grid systems only, ordinary hazard, 2,000 SF, sched, 40 steel pipe	1.710.0000 SF	22.583.71
Elevator	1,710.0000 35	22,303.71
Elevator Electric traction freight elevators, base unit, standard finish, 4000 lb, 200 fpm, 3 stop	1.0000 EA	213,456.99
Ergo-compliant Storage Container Pad		
Piles		
Piling special costs, cutoffs, concrete piles, plain	4.0000 EA	505.14
Prestressed concrete piles, square, 40' long, 12" square, priced using 200 piles, excludes pile caps or mobilization	1,672.0000 VLF	78,960.53
Concrete Structural concrete, in place, chimney foundation, industrial, maximum, includes forms(4 uses), reinforcing steel, and finishing	6.0000 CY	4,206.11
Water Supply and Distribution System	0.0000 C1	4,200.11
Reservation Yard Potable Water Piping		
Public Water Utility Distribution Piping, polyvinyl chloride pressure pipe, 1", class 200, SDR 21, includes trenching to 3' deep	4.600.0000 LF	49.655.25
Water Utility Distribution Fire Hydraunts, yard hydrant, flush, non-freeze, above ground, 1" connection, 4' depth of bury, excludes excavation and backfill	3.0000 EA	1,098.90
Structural concrete, in place, equipment pad, 3' x 3' x 6", includes forms, reinforcing steel, concrete, and finishing	3.0000 EA	528.87
Public Water Service		
Public Water Utility Distribution Piping, fitting, 45 degree bend, ductile iron, cement lined, mechanical joint, 6" diameter, class 50 water piping Public Water Utility Distribution Piping, butterfly valves cast iron, with extension box, 6" diameter	2.0000 EA 3.0000 EA	1,100.10 4,467.93
Water Service Connection, ductile iron, cement lined, 8" main, 6" branch, class 50 water piping, drill and tap pressurized main (labor only), excludes excavation or backfill	1.0000 EA	4,467.93 668.72
Water Service Connection, tapping crosses with rubber gaskets, 8" x 6", excludes excavation and backfill	1.0000 EA	2.987.99
Structural excavation for minor structures, bank measure, for spread and mat footings, elevator pits, and small building foundations, sandy clay or loam, 1/2 C.Y. bucket, machine excavation, hydraulic backhoe	20.0000 BCY	521.72
Compaction, around structures and trenches, 2 passes, 18" wide, 6" lifts, walk behind, vibrating plate	20.0000 ECY	36.47
Concrete Pipe Kicker	4.0000 EA	38.69
Fire Hydrants Fire hydrants, two way, breakable, 5'-0" depth, 6", includes mechanical joints, excludes excavation and backfill	1.0000 EA	4,681.79
Concrete Pipe Kicker	4.0000 EA	38.69
Sanitary Sewer and Distribution System		22.00
earnary earner and electrostics eyocom		

Print Date Sat 27 July 2019
U.S. Army Corps of Engineers

Eff. Date 6/6/2019
Project IHNCSD: Inner Harbor Navigation Canal Lock Replacement - Shallow Draft

Eff. Date 6/6/2019 Project IHNCSD: Inner Harbor Navigation Canal Lock Replacement - Shallow Draft

New Report New Section Page 10

Time 13:08:43

Description	Quantity	UOM	ProjectCost
Sanitary Sewer and Distribution System Pump, grinder system, simplex, 9 GPM at 60 PSIG, 91 gallon tank, includes check valve, tank, standard controls, alarm/disconnect panel with wire, excludes excavation Pump, grinder system with manway, 18 GPM at 60 PSIG, 43" ID, 48" high, for 150 gallon tank, includes check valve, tank, standard controls, alarm/disconnect panel with wire, excludes excavation	1.0000 1.0000		6,529.53 16,154.54
Sanitary Treatment and Distribution System- WBV90 Sewage Treatment Systema and Yard/Bridge Piping to Building	1.0000	0 LS	801,043.38
Earthwork for Structures			
Lock Site-Backfill Granular Backfill Clay Backfill	467,320.0000 65,710.0000		9,193,134.58 2,052,712.51
Foundation Protection Rip-rap and rock lining, random, broken stone, machine placed for slope protection Surfacing Geosynthetic soil stabilization, geotextile fabric, woven, heavy duty, 600 lb. tensile strength	60,000.0000 12,000.0000 36,000.0000	0 TON	2,279,755.16 633,892.73 240,522.94
Foundation Work			
Sheet Piling PZ-22 Remove Piles Unloading Piling Driving Sheetpile PZ 22 Material Price (includes delivery)	33,000.0000 421.0526 33,000.0000 726,000.0000	6 EA 0 SF	39,964.86 16,684.56 68,878.75 1,063,007.18
Chamber Monoliths 24" PPC Piles Concrete Pile Unloading Cutoff Drive heads Precast Concrete Pile Installation Pre-Cast Concrete Pile - 24"x24"	792.0000 792.0000 120,750.0000 120,750.0000	0 EA 0 VLF	71,734.07 44,987.40 2,320,316.29 11,618,404.93
Gatebay Monoliths 24" PPC Piles Concrete Pile Unloading Cutoff Drive heads Precast Concrete Pile Installation Pre-Cast Concrete Pile - 24"x24"	933.0000 933.0000 223,920.0000 223,920.0000	0 EA 0 VLF	84,504.91 52,996.52 4,302,817.60 21,545,285.57
Storage Platform 24" PPC Piles Concrete Pile Unloading Cutoff Drive heads Precast Concrete Pile Installation Pre-Cast Concrete Pile - 24"x24"	16.0000 16.0000 1,600.0000 1,600.0000	0 EA 0 VLF	1,449.17 908.84 30,745.39 153,949.88
Lock Gates & Operating Machinery			
Metals			
Sector Gates Fabricated Steel	1,335,000.0000	0 LB	4,881,475.24
Maintenance Bulkheads Fabricated Steel Structural steel marine placement Composite Timber Fenders 8"X 12" (On Gates)	1,960,000.0000 176.0000		7,166,810.08 150,537.83

Print Date Sat 27 July 2019

U.S. Army Corps of Engineers

Eff. Date 6/6/2019

U.S. Army Corps of Engineers

Time 13:08:43

Project IHNCSD: Inner Harbor Navigation Canal Lock Replacement - Shallow Draft

New Report

New Report

New Report

Description	Quantity UOM 2.9040 MBF	ProjectCost
Wood framing, heavy mill timber, beams, built from 8" lumber, multiple 4" x 12"	2.9040 MBF	19,117.65
Machinery  Gate Operating Machinery  Gate machinery	1.0000 EA	1,413,848.55
Concrete Floating Guidewall		
Cofferdam		
Sheetpile Unloading steel sheet piling PZ-35 driving sheet piling pulling sheet piling	26,880.0000 SF 26,880.0000 SF 26,880.0000 SF	1,270,016.22 234,518.37 117,259.18
<b>Bracing</b> Structural steel member, 100-ton project, 1 to 2 story building, W27x94, A992 steel, shop fabricated, incl shop primer, bo	Ited connections 3,723.0000 LF	993,505.39
Guidewall		
HP 14 X 73 HP 14 X 73 Pile Unloading H Pile Installation Paint H Piles, Coal-Tar Epoxy	744,600.0000 LB 410.0000 EA 10,200.0000 VLF 42,804.0000 SFC	1,061,923.29 37,135.06 145,186.57 183,136.84
Precast Concrete Pontoons Precast Concrete Pontoons	2,500.0000 CY	4,342,639.15
Concrete, In Place Concrete Wall	1,666.0000 CY	1,100,209.45
Sand Fill Excavation, bulk, dragline, bank measure, unclassified soil, 3 C.Y. bucket, excavate Granular Fill	600.0000 BCY 600.0000 CY	1,393.69 16,062.63
Pontoon Timbers (12 x 12) Wood framing, heavy mill timber, girders, structural grade, 12" x 12"	31.2000 MBF	144,621.37
Miscellaneous Metals Steel Plates installation (Corner Protection, Vertical Seals, Walkways)	135,000.0000 LB	1,357,026.49
Timber Guidewalls		
Guidewalls Timber piles, friction or end bearing, treated, 12 lb. creosote/C.F., 13" butts, 6" points, 60 - 69' long, ASTM class B, exclusive Wood framing, heavy mill timber, girders, structural grade, 12" x 12" Piling, connection hardware Wood framing, heavy mill timber, beams, built from 3" lumber, multiple 3" x 12"	des mobilization or demobilization  44,500.0000 VLF 6.9200 MBF 55.3600 LB 16.6800 MBF	2,932,904.97 32,076.28 105.27 67,879.86
End Cells		
Sheet Piling PS-31 Remove Piles Unloading Piling Driving Sheetpile - PS-31 PS 31 Material Price (includes delivery)	0.0000 SF 794.4569 EA 73,000.0000 SF 2,263,000.0000 LB	0.00 39,804.23 238,842.33 3,313,478.31

Print Date Sat 27 July 2019 Eff. Date 6/6/2019

## U.S. Army Corps of Engineers Project IHNCSD: Inner Harbor Navigation Canal Lock Replacement - Shallow Draft New Report

Time 13:08:43

New Section Page 12

Description	Quantity	UOM	ProjectCost
Concrete Cap Concrete	4,000.0000	CY	2,641,559.31
Sand Fill Excavation, bulk, dragline, bank measure, unclassified soil, 3 C.Y. bucket, excavate Granular Fill	26,000.0000 26,000.0000		60,393.05 696,047.12
Lock Structure			
Concrete			
Chamber Monoliths Concrete Stabilization Slab	7,280.3500	CY	2,259,109.96
Gatebay Monoliths Concrete Stabilization Slab	13,632.3000	CY	4,230,135.18
Storage Platform Concrete	200.0000	CY	95,580.85
Metals			
Wall Armor Steel Plates installation (Corner Protection, Vertical Seals, Walkways)	400,000.0000	LB	2,907,930.00
Floating Mooring Bits Steel Plates installation (Corner Protection, Vertical Seals, Walkways)	115,000.0000	LB	836,029.88
Miscellaneous Metals Steel Plates installation (Corner Protection, Vertical Seals, Walkways)	700,000.0000	LB	5,088,877.51
Culvert Valves & Oper. Mach.:			
Metals			
Culvert Roller Gates (4)  RxR Roller Gates Fabricated Steel, RxR Roller Gate	1.0000 104,000.0000		54,571.92 1,307,840.30
Culvert Maint. Bulkhead (4) Fabricated Steel	88,000.0000	LB	321,775.15
Culvert Invert Screens (4) Fabricated Steel	118,000.0000	LB	431,471.22
Mechanical			
Culvert Valve Machinery Hydraulic system, materials Installation of sector gate machinery	1.0000 320.0000		279,367.07 596,994.58
Piping Systems			
Mechanical Washdown System	1.0000	) EA	44,182.77
Power and Lighting Systems:			
Electrical			

Print Date Sat 27 July 2019

U.S. Army Corps of Engineers

Eff. Date 6/6/2019

Project IHNCSD: Inner Harbor Navigation Canal Lock Replacement - Shallow Draft

Eff. Date 6/6/2019

Project IHNCSD: Inner Harbor Navigation Canal Lock Replacement - Shallow Draft

New Report

Description

Panelboards, 1 phase 3 wire, main circuit breaker, 120/240 V, 225 amp, 30 circuits, NQOD, incl 20 A 1 pole plug-in breakers Panelboards, 1 phase 3 wire, main circuit breaker, 120/240 V, 400 amp, 30 circuits, NQOD, incl 20 A 1 pole plug-in breakers Panelboards, 1 phase 3 wire, main circuit breaker, 120/240 V, 400 amp, 42 circuits, NQOD, incl 20 A 1 pole plug-in breakers Panelboards, 3 phase 4 wire, main circuit breaker, 120/240 V, 400 amp, 42 circuits, NQOD, incl 20 A 1 pole plug-in breakers Panelboards, 3 phase 4 wire, main circuit breaker, 120/208 V, 100 amp, 30 circuits, NQOD, incl 20 A 1 pole plug-in breakers Disconnect switch, 3 pole fusible, 200 amp, to 125 HP motor, 600 volt Junction Box/Pull Box Exhaust fan Magnetic Motor Starter Limit Switch	1.0000 EA 1.0000 EA 1.0000 EA 1.0000 EA 3.0000 EA 3.0000 EA 7.0000 EA 8.0000 EA	6,536.76 8,690.06 9,572.93 4,900.87 9,088.97 8,678.47 11,651.22 29,422.65 58,239.54
Lights Emergency light units, battery pack, w/two 6 V floodlights, (Type 603) Floodlights, exterior, induction lamp, 150 watt, floor mtd, mount with swivel bracket, incl ballast and lamp Fluorescent fixture, interior, troffer parabolic lay-in, 2-U32 W T8, 2' W x 2' L, incl lamps, mounting hardware and connections Fluorescent fixture, interior, troffer parabolic lay-in, 3-32 W T8, 2' W x 4' L, incl lamps, mounting hardware and connections High pressure sodium fixture, interior, surface, round, 100 W, incl lamps, and mounting hardware LED fixtures, interior, strip, surface mounted, 40 watt, one light bar 4' long, incl lamps, mounting hardware and connections	1.0000 EA 4.0000 EA 1.0000 EA 11.0000 EA 4.0000 EA 3.0000 EA	514.08 10,623.35 372.94 4,610.71 6,134.91 1,286.38
Lightning Protection System Lightning Protection System	2.0000 EA	26,509.66
Navigation Marine Lantern Navigation Signal Fog Detector Traffic Signal	1.0000 EA 1.0000 EA 1.0000 EA 1.0000 EA	7,192.31 2,655.50 949.38 2,722.45
Conduit and Wiring Allow \$200,000 for conduits and wiring for all items	1.0000 EA	353,462.14
Web Camera System Install Cameras Web Camera System	2.0000 EA 1.0000 LS	2,691.22 79,262.12
Emergency Power Generator set, diesel, 3 phase 4 wire, 277/480 V, 1000 kW, incl battery, charger, muffler, automatic transfer switch & day tank, excl conduit, wiring, & concrete	1.0000 EA	363,791.57
Traffic Signals Traffic signals, intersection, LED, mast, programmable, R/L lane control, includes all labor, material and equipment for complete installation	2.0000 EA	1,038.93
Program Logic Control (PLC), Hardware Backup Controls Program Logic Control (PLC), Hardware Backup Controls	1.0000 EA	1,087,779.72
Assosciated General Items		
Demolition of Existing Lock, St Claude bridge Lock Wall Demolition Debris Removal Bridge Demolition & Removal Guidewall & Dolphin Removal	1.0000 LS 1.0000 LS 1.0000 LS 1.0000 LS	3,628,288.83 4,195,595.56 1,021,505.57 712,226.20
Tree Removal Tree Removal	1.0000 LS	53,019.32

Time 13:08:43

New Section Page 13

UOM ProjectCost

Quantity

U.S. Army Corps of Engineers Project IHNCSD: Inner Harbor Navigation Canal Lock Replacement - Shallow Draft

New Report

New Section Page 14

Time 13:08:43

Description	Quantity UON	I ProjectCost
Site Work		
Permanent Mooring Facil. Cells Timber piles, friction or end bearing, treated, 12 lb. creosote/C.F., 13" butts, 6" points, 60 - 69' long, ASTM class B, excludes mobilization or demobilization Wood framing, heavy mill timber, girders, structural grade, 12" x 12" Piling, connection hardware Wood framing, heavy mill timber, beams, built from 3" lumber, multiple 3" x 12"	48,000.0000 VLF 22.0000 MBF 176.0000 LB 28.0000 MBF	340.50
Demolition of Coast Guard Facility Coast Guard Facility	1.0000 LS	3,497,507.84
Tow Assistance Tugs Tug Low Usage LONG TERM RENTAL	175,104.0000 HR	60,345,318.10
Roads, Railroads & Bridges		
St. Claude Bridge Replacement		
Bascule Bridges - Main and Temporary Channel		
Demolition (Ramps only) Demolition (Ramps only)	1.0000 JOB	636,762.04
Structural Steel, Bascule Gate Leafs Decking Installation Decking Steel	106.1900 TON 11,480.0000 SF	427,746.82 1,218,546.05
Concrete, Gate Leaf Piers 4" Stabilization Slab Concrete, In Place, Includes Forming, Placement, Concrete	281.9600 CY	69,899.95
Piling, 18" Diameter Pipe Piles, Bridge Piers 1, 2, 3 Pile Unloading - 18" pipe piles (Landbased) Pile Installation (Landbased) 18" Pipe Pile, 1/2" thk (includes delivery) 18" Pipe Pile Splicing Paint Steel Pipe Piling, CTE	336.0000 EA 40,488.0000 VLF 3,815,002.8000 LB 336.0000 EA 79,128.0000 SFC	30,432.64 576,305.29 5,440,827.75 291,825.35 413,782.13
Concrete, Approach Ramps, Bents Pile Unloading - 18" pipe piles (Landbased) Pile Installation (Landbased) 18" Pipe Pile, 1/2" thk (includes delivery) 18" Pipe Pile Splicing Paint Steel Pipe Piling, CTE	486.0000 EA 51,030.0000 VLF 4,814,170.0000 LB 486.0000 EA 45,781.0000 SFC	30,657.57 512,778.90 5,103,474.39 313,757.71 177,951.32
Concrete, Decking, Barriers, Girders Guardrail, 1-1/2" Diameter Pipe	2,160.0000 EA	177,369.33
Steel Sheet Piling, PZ-40 Retaining Wall Sheetpile Unloading Sheet Piles (Landbased) Driving Sheetpile - PZ-40 (Landbased) PZ-40 Material Price (includes delivery) PZ-40 Splicing Cutting Sheet Piling Remove Sheet Piles (Landbased) Temporary Retaining Structures (TRS) for Bridge Piers - Assume PZ-35 Sheetpile - Piers 1, 2, 3	426.0000 EA 70,000.0000 SF 2,800,000.0000 LB 426.0000 EA 700.0000 LF 35,000.0000 SF	16,880.60 133,633.93 4,099,752.21 221,995.1 12,159.39 42,386.97

Print Date Sat 27 July 2019

U.S. Army Corps of Engineers

Eff. Date 6/6/2019

U.S. Army Corps of Engineers

Time 13:08:43

Project IHNCSD: Inner Harbor Navigation Canal Lock Replacement - Shallow Draft

New Report New Section Page 15

Description	Quantity	MOU	ProjectCost
Fabricated Steel Installation Fabricated Steel Fabricated Steel	50.0000 100,000.0000 50.0000	LB	136,223.99 359,393.86 68,112.00
Structural Excavation and Granular Backfill for Bridge Piers 1, 2, 3 Structural Excavation, Bridge Piers Structural Granular Backfill, Bridge Piers Structural Granular Backfill, Material Structural Granular Backfill, Material	33,000.0000 16,000.0000 16,000.0000 33,000.0000	CY	139,193.95 144,698.83 158,307.42 240,170.69
Channels and Canals			
Canals			
Canals - Dredging (Excavation)			
Canals - Dredging (Excavation) 10 CY Bucket Scow Hauling	80.1714 80.1714		716,703.29 2,724,318.06
Bank Stabilization			
Site Work-North Bypass Geosynthetic soil stabilization, geotextile fabric, woven, heavy duty, 600 lb. tensile strength	22,000.0000	SY	199,977.59
Levees and Floodwalls			
Associated General Items:			
Floodwalls (West & East IHNC)			
T-Wall Concrete Concrete Slab Concrete Slab Concrete Stabilization Slab Expansion Joint 3-Bulb Waterstop - 3/8" thk x 9" wide Concrete Wall	27,061.0000 2,909.0000 41,735.5400 18,831.8900 20,926.0000	CY SF LF	16,051,989.79 973,595.30 130,354.91 266,676.74 17,754,959.81
18" Dia. Steel Pipe Piles Pile Unloading Pile Installation Paint Piles, Coal-Tar Epoxy 18" Pipe Pile, 1/2" thk (includes delivery)	5,887.0000 672,245.0000 831,834.0000 62,854,907.5000	VLF SFC	533,205.13 9,568,720.36 3,559,000.41 89,641,539.70
Sheet Piling PZ-22 Remove Piles Unloading Piling Driving Sheetpile PZ 22 Material Price (includes delivery) Paint Piles, Coal-Tar Epoxy	342,490.0000 5,700.0000 342,490.0000 7,534,780.0000 256,500.0000	EA SF LB	414,774.67 225,867.21 714,857.03 11,032,403.92 1,097,434.83
Pile Tests Pile test Setup Tension/Compression Tests	1.0000 24.0000	0.000	260,558.35 1,459,126.75
Levee Setback Reshaping	50,000.0000	CY	116,305.48

Print Date Sat 27 July 2019

U.S. Army Corps of Engineers

Eff. Date 6/6/2019

U.S. Army Corps of Engineers

U.S. Army Corps of Engineers

Time 13:08:43


Project IHNCSD: Inner Harbor Navigation Canal Lock Replacement - Shallow Draft

New Section Page 16

New Report

Description	Quantity	MOU	ProjectCost
Compacted Embankment Fill For Floodwalls Embankment	167,900.0000	CY	5,245,022.52
Compacted Embankment Fill for Levee Access Roads Embankment	20,000.0000	) CY	624,779.34
Demolition of Existing Floodwall			
Demolition of Concrete Floodwall  Building demolition, commercial building, reinforced concrete, with pneumatic tools, includes 20 mile haul, excludes foundation demolition, dump fees  Landfill Disposal Fee	12,627.0000 12,627.0000		251,183.41 84,038.26
Extract Steel Sheet Piling Remove Sheet Piles (Landbased) Unloading Sheet Piles (Landbased)	26,500.0000 662.5000		32,092.99 26,252.11
Extract 12" Concrete Piles Concrete Pile Loading (Landbased) Precast Concrete Pile Removal (Landbased)	36.0000 2,700.0000	71 (1 - 1) - 1) - 1	3,260.64 25,941.42
Backfill Embankment	3,200.0000	CY	137,177.23

## **Project Construction Schedule**



## **Cost and Schedule Risk Analysis**

				Project Cost Project Schedule								
Risk No.	Risk/Opportunity Event	Concerns	PDT Risk Conclusions, Justification	Likelihood*	Impact*	Risk Level*	Rough Order Impact (\$)	Likelihood*	Impact*	Risk Level*	Rough Order Impact (mo)	Variand Distribut
	Contract Risks (Internal	Risk Items are those that are generated, caus	ed, or controlled within the PDT's sphere of influe	ence.)								
	PROJECT & PROGRAM MGMT											
PM1	Scope incomplete	possible addition of new Florida Ave Bridge	At this time there is no possibility the bridge is not included in the project. This addition would require reauthorization of the project.	Very Unlikely	Significant	LOW		Very Unlikely	Marginal	LOW		
PM2	Adequate staff during PED	critical staff changes at crucial points of the project	The current workforce in MVN is nimble enough to absorb fluctuations in work load.	Unlikely	Negligible	LOW		Unlikely	Negligible	LOW		
PM3	Project delivery on an accelerated schedule	reduced QC, cost and schedule savings not analyzed due to time restraints	MVN is accustomed to accelerated schedules however the cost to PED can increase to obtain necessary quality to the project documents. Since the schedule is accelerated it will not be impacted. Use 15% of PED.		Marginal	MODERATE	\$16,478,782	Unlikely	Negligible	LOW		
PM4	Scope objectives	are objectives finalized	The lock size is finalized however some modeling needs to occur to finalize design. No scope changes are anticipated. Hydraulics modeling needs to be completed.	Very Unlikely	Negligible	LOW		Very Unlikely	Negligible	LOW		
PM5	Project development by several sources	coordination/QC of design features on multiple project features	Coordination between Federal and Private organization during PED cause impacts to quality control and completion of the product. For more than a decade A/E's have been imbedded in MVN projects performing adequately.	Unlikely	Negligible	LOW		Unlikely	Negligible	LOW		
PM6	Unplanned work that must be accommodated	additional work to appease maritime, civic, city, business	Additional features such as bike paths, sound proofing, green spaces, guide walls, lighting, light rail transportation, and mitigation projects could be included. This would have impacts on cost and schedule. Use 10% of construction cost for the ROM cost value and 36 months for the ROM schedule value.	Likely	Marginal	MODERATE	\$71,292,804	Likely	Significant	HIGH	36 Months	
PM7	Dredging Scope	Excavation of bypass channel under bridges	Bridge clearances in this area will require land based equipment under the bridges to excavate the by pass channel.	Likely	Negligible	LOW	\$200,000	Likely	Negligible	LOW		
	CONTRACT ACQUISITION RISKS											
CA1	Undefined acquisition strategy	type of contracts resulting in delayed awards	Negotiated Procurements, Small Business, low bid, Design Bid Build, Early Contractor Involvement are possible vehicles to award features of work. The resulting impacts will be low to cost and schedule.	Unlikely	Marginal	LOW	\$35,646,402	Unlikely	Marginal	LOW	1 Months	

Ī	1		I	Í	İ			i i			7	Í
CA2	Numerous separate contracts	numerous contracts impacts qualified contractor pool, mobilization cost	Obtaining qualified contractors to complete a project of this scope additional contracts on smaller features.  Having numerous contracts can spread thin the Contracting Offices resources to respond. Use 50% of construction mobilization costs.	Likely	Marginal	MODERATE	\$15,032,354	Likely	Marginal	MODERATE	24 Months	
CA3	Limited Competition on Dredging	Due to the small dredge quantity (~ 500,000 cy), competition will be limited.	Lack of competition foregoes the lowest bid process and hinders achieving the lowest cost to the government for this project. Therefore we can anticipate dredge cost can be 25% higher than the IGE.	Likely	Significant	HIGH	\$9,956,417	Likely	Negligible	LOW	3 Months	
CA4	Competition for Structural	lack of competition between bidders on structural contracts	From MVN historical data, there will be healthy competition between bidders	Very Unlikely	Marginal	LOW		Very Unlikely	Marginal	LOW		
	TECHNICAL RISKS	oo maada	competition activities and activities	very enimery	Margina			vory criminary	marginar			
TL1	Geotechnical	additional borings/testing changes design	The borings for the structure are adequate for the current design. Confidence is high. A pile optimization study will be conducted to reduce cost. Borings for the bridge and floodwall will have to be revisited to refine the design. A cost savings in construction is anticipated because of a conservative design.	Very Unlikely	Negligible	LOW		Very Unlikely	Negligible	LOW		
TL2	Geotechnical Stability Analysis	No analysis on T-wall design in General Re- evaluation Report	Stability analysis performed during PED MAY reveal some unbalanced loads, requiring increases in T wall pile foundation cost. The cost for pile foundations can have up to a 25% increase to foundation cost may be obtained if unbalanced are found.	Likely	Marginal	MODERATE	\$38,421,267	Unlikely	Marginal	LOW		
TL3	Structural	refined design, changes design, construction sequence, revise design to account for RSLR	Once the design is refined and the floodwalls are broken up into reaches, there will be some changes to the quantities. Bridge design will be refined in PED with the use of an A/E expert for the bridge which equates to a cost savings. The cofferdam design is based upon good soils investigation and testing but some assumptions will need to be refined. Jet grouting will need to be refined and may change the scope of that work. Reference RSLR: Technical Point of Contacts/Lead Designers state that the RSLR impact to redesign and additional quantities is likely with marginal impact to cost and likely with negligible impact to schedule.	Likely	Marginal	MODERATE	\$60,000,000	Likely	Negligible	LOW	12 Months	
TL4	Mechanical/electrical design	refined design changes design	No design was performed. Data was used from other projects with similar elements. Detailed design will be done during PED.	Very Likely	Marginal	MODERATE	\$6,548,432	Very Likely	Negligible	LOW		
TL5	Design by others	E&D impacts due to re-designs/revisions	High quality design firms that have the technical capabilities to perform the work. Over the shoulder review will be performed to maintain QA. Other Districts will be utilized. Inland Navigation Design Center will be involved with the design and will used a qualified pool on designers with inland navigation experiences that will be used.	Very Unlikely	Marginal	LOW		Very Unlikely	Marginal	LOW		

			ı	1	1		1			i-	•	Ī
TL6	Accurate as-built data	impacts to design of project features, demolition of existing lock system, existing buildings	As built drawing may not capture possible utilities near the St Claude bridge and lock structure. Buildings may contain possible contaminated materials that need special handling and disposal.	Very Likely	Marginal	MODERATE	\$50,000,000	Very Likely	Marginal	MODERATE	12 Months	
TL7	Accurate existing utility	, , , , ,	oponarramy and anopodar			LOW	<b>400,000,000</b>			LOW	.2	
IL/	data	scope revisions to capture additional utilities		Very Unlikely	Negligible			Very Unlikely	Negligible			
TL8	Hazardous/Contaminated Material	impacts of additional HW in dredged and excavated materials	There is a possibility of HTRW material being wasted in the lock area due to the amount of vessel traffic currently using the facility. The last sampling was taken in 2007.	Unlikely	Significant	MODERATE	\$50,000,000	Likely	Significant	HIGH	24 Months	
TL9	Lack of subsurface info for under water/ in water work	sufficient info for cofferdam, demolition, dredging work	There is current accurate info and as built drawings that have sufficient subaqueous.	Very Unlikely	Marginal	LOW		Very Unlikely	Marginal	LOW		
TL10	Dredging and Bank Stabilization Quantities	accuracy of design/quantities	Design quantities have not been assessed by Civil Branch at this time. Therefore quantities can vary greatly until final alignments and surveys have been completed. This quantity variation will affect the dredging and the bank stabilization quantities. As per the PDT a 15% increase in quantities will be used. The increase in time to the contract for this quantity increase is 1.5 months which is negligible.	Likely	Marginal	MODERATE	\$4,912,309	Likely	Negligible	LOW		
TL11	Dredge Scope	Changes in disposal plan, location and capacity.	Currently the disposal plan features all dredge material to be placed in the Mississippi River. If the current location is adjusted assume an additional 5,000 LF of dredge pipeline. There is a quantity of contaminated material that is barge hauled to Venice, LA for final disposal. If this facility is unavailable another facility 50 more miles away can be used. A change in scope only adds 1 month to the schedule, negligible.	Likely	Marginal	MODERATE	\$3,541,684	Likely	Negligible	LOW		
TL12	Hydraulic ship simulation of construction by pass channel	The simulation was last done in 1997 report but no new one has been completed. The simulation will be done during PED.	The ship simulation will be completed during PED. Tug assist may be show as necessary from the simulator.	Unlikely	Marginal	LOW		Unlikely	Negligible	LOW		
TL13	Hydraulic filling and emptying system	Physical model is required during PED to validate Hawser forces on barge tows.	If excessive Hawser forces are found during modeling significant changes will need to be made to port system and or sill elevation in the chamber.	Very Unlikely	Significant	LOW		Very Unlikely	Significant	LOW		
	LANDS AND DAMAGES RISKS	, and the second			Ĭ							
LD1	Real estate/easement acquisition	property ownership/objections to appraisals	Only acquiring in fee 3 properties on the west side of the project. Relocation assistance i.e., new home, moving expenses, etc. If the properties cannot be obtained condemnation would ensure impacting the schedule.	Very Unlikely	Negligible	LOW	\$0	Likely	Marginal	MODERATE	12 Months	
LD2	Real estate plan	has the RE plan been defined?	Awaiting information regarding compensable interest for utility relocations. Traffic plans impact to right of entry for landowners. Some homeowners shall be temporarily relocated for safety and access concerns for 6 months at a time. Roughly 25 residents and two business can have temporary access issues. From discussions an impact of \$500,000 would impact the project.	Very Unlikely	Negligible	LOW	\$0	Likely	_ Significant	HIGH	24 Months	

LD3	Utility Relocation Plan  REGULATORY AND	delays to relocations impact project features, known utilities locations differ and impact design/construction, abandoned utility locations impact design/construction	Waterlines, communications, power lines, sewer lines, private gas and petroleum lines. During the Katrina reconstruction, many project site utilities were verified and some were capped, removed and abandoned. This results in less utilities than was quantified during the 1997 report. Therefore an unknown utility is unlikely. Known utilities without verified survey information to determine below channel elevations are real.	Likely	Marginal	MODERATE	\$70,000,000	Likely	Marginal	MODERATE	18 Months	
	ENVIRONMENTAL RISKS											
REG1	Project located in high sensitivity area to air/water/land/noise impacts	additional costs to not exceed environmental thresholds	Due to the proximity of residence construction activities can disturb the surrounding area. Truck hauling, pile driving, dredging and other construction activities may be restricted to certain times of the day for short time periods to limit impacts. Work schedule for construction is 5 days per week, 8 hours per day. Likelihood of a less aggressive work schedule is possible. Activities that do not impact the surrounding area can continue for longer periods of the day. A 1% increase of cost on heavy construction items could be impacted resulting in a \$5M increase. Currently the dredging is executed during the daylight hours and a possible 7 days per week. This schedule has occurred in the past. Reduction in dredge plant running times occurs in ET-5.	Likely	Negligible	LOW		Likely	Marginal	MODERATE	18 Months	
REG2	Containments of concern	cost and schedule impacts for project foot print materials	If dredged material is consistent with assumed characteristics then minimal changes are anticipated. No reason to assume changes have occurred.	Very Unlikely	Negligible	LOW		Very Likely	Negligible	LOW		
REG3	Multi agency review of permits	delays to permit approvals	Schedule or cost changes are not a concern. A Storm Water Protection Plan Section 402 Clean Water Act (permit) and a Bridge Permit with the US Coast Guard (a memorandum). Products would be developed in MVN and processed accordingly	Very Unlikely	Negligible	LOW		Very Unlikely	Negligible	LOW		
REG4	Historic/cultural site	unexpected find of historic/cultural significance delays project	The St. Claude Ave. Bridge, The Holy Cross National Register Historic District, Bywater National Register Historic District, Sewerage and Water Board, Sewerage Pump Station B and the Judge Seeber Bridge/LA 39/ N. Claiborne Ave. are the identified at this time. However some project features have not been explored. After investigation additional cost and schedule impacts can occur.	Likely	Marginal	MODERATE	\$5,000,000	Likely	Marginal	MODERATE	18 Months	
REG5	Environmental and water quality issues	environmental impacts from dredging and disposal of industrial corridor channel bottom	A water quality certificate has been obtained. Unless features of the project change substantially an amended certificate will have to be crafted. The dredge material disposal plan is not likely to change.	Very Unlikely	Negligible	LOW		Very Unlikely	Negligible	LOW		
	CONSTRUCTION RISKS											

				_	-		_	_			_	_
CO1	Adequate staging areas	possible multiple concurrent construction contracts strain available site staging areas	Current available vacant land and warehouse areas surrounding the project site should be of sufficient size and quantity to support multiple contractor's needs.	Unlikely	Marginal	LOW		Unlikely	Marginal	LOW		
CO2	Critical fabrication and delivery	specialized fabrication/materials/delivery of vital lock and bridge components may increase cost and delay construction	Some specialized fabrication may be needed for the lock and bridge construction but the fabrication materials and methods are not unique and have been successfully completed on previous projects. The construction schedule is flexible to allow for sufficient lead time for fabrication and delivery of such items.	Unlikely	Marginal	LOW		Unlikely	Marginal	LOW		
CO3	Transportation/haul routes constricted or unusable during periods of time		There will be reduced transportation facilities available but minimal impacts	Likely	Negligible	LOW		Likely	Negligible	LOW		
CO4	Innovative project construction	innovative construction methods increase cost and time	The construction methods are similar to what have been successfully used on previous local major structural projects. MVN Corps personnel and contractors are versed in necessary construction methods.	Unlikely	Marginal	LOW		Unlikely	Marginal	LOW		
CO5	Navigation traffic	constant marine traffic impacting project construction efficiency	Cofferdam, channel dredging and lock construction will not be impacted by marine traffic. The new St Claude Bascule bridge construction may be impacted by marine traffic.	Likely	Marginal	MODERATE	\$5,000,000	Likely	Negligible	LOW	6 Months	
CO6	Marine construction	marine based construction may be more expensive and create longer construction durations	The marine based construction needed for this project is typical for the MVN District and has been successfully deployed before by contractors on minor and major construction projects.	Very Unlikely	Negligible	LOW		Very Unlikely	Negligible	LOW		
CO7	Inefficient contractors	cost and schedule impacts occur due to poorly performing contractors	The procurement process should be able to select the most highly qualified contractors with a proven track record of performance.	Very Unlikely	Significant	LOW		Very Unlikely	Significant	LOW		
CO8	Modifications	large scope will produce modifications	The large scope of the project will result in numerous modifications	Very Likely	Marginal	MODERATE	\$70,000,000	Very Likely	Marginal	MODERATE	24 Months	
	ESTIMATE AND SCHEDULE RISKS											
ET1	Labor availability/wages	labor pool shortage and wage increases during construction	A ten year project will see fluctuations in the availability of trained and qualified labor pools but if necessary, some labor training can be done by the contractors.  Wage increases will occur over the life of the project and the costs should reflect escalations.	Very Likely	Marginal	MODERATE	\$23,814,038	Unlikely	Marginal	LOW		
ET2	Material availability/escalation	material shortage and price increases	A ten year project might see fluctuations in the availability of certain materials and material price escalation will occur.	Very Likely	Significant	HIGH	\$37,734,255	Unlikely	Marginal	LOW		

ET3	Cost and schedule estimate construction phasing	variations in construction sequencing and/or phasing may impact cost, duration	construction sequencing changes might impact cost and durations but such changes will have minor impacts	Unlikely	Marginal	LOW		Unlikely	Marginal	LOW		
ET4	Estimate reasonableness of crews and productivity	crew and productivity revisions impacts cost and schedule	estimate of cost and schedule will be based upon historical crew sizes and production rates for similar types of work. MVN has a wealth of third type of data concerning heavy civil construction	Unlikely	Marginal	LOW		Unlikely	Marginal	LOW		
ET5	Dredge Plant Running Time	Fluctuation in dredge plant running time may occur due to various factors.	Unknown underground obstructions and debris could impact dredge plant running time thus impacting dredging cost. Dredging shall occur only during daytime hours to lower noise levels. We will assume a 25% reduction in dredge running times.	Likely	Marginal	MODERATE	\$2,624,504	Likely	Negligible	LOW	2 Months	
ET6	Dredge Production Rates	Dredge plant production can vary.	Dredge production can vary from the ones used in the estimate. A dredge plant of lower capacity could actually construct the work. Assume a 30% reduction in production rates.	Likely	Significant	HIGH	\$9,384,162	Likely	Negligible	LOW		
	Programmatic Risks	(External Risk Items are those that are gene influence.)	rated, caused, or controlled exclusively outside th	ne PDT's sphere	e of							
PR1	Adequacy of project funding/ funding stream	level of project funding priority / yearly allocation	historic data shows that long term programs have received funding cuts, Inland Waterway Trust Fund has a limited fund balance remaining and other ongoing projects share the funding	Very Likely	Critical	HIGH	\$150,000,000	Very Likely	Critical	HIGH	60 Months	
PR2	Local community opposition	project opposition impacts project construction	Because of the cultural and historical concerns the local community can oppose the demolition of portions of the project and stymie construction startup	Very Likely	Marginal	MODERATE	\$10,000,000	Very Likely	Marginal	MODERATE	12 Months	
PR3	Political factors at all levels of government	politicians opposed to project delay construction	currently, the political crowd is in favor of the project but civic opposition may change mindsets	Likely	Marginal	MODERATE	\$10,000,000	Likely	Marginal	MODERATE	12 Months	
PR4	Fuel price escalation	Fuel is a volatile cost and can greatly affect the cost of this project.	A ten year project will see fluctuations in fuel prices. Fuel could increase or decrease altering the cost. We assume an increase of \$2.25 or a decrease of \$0.75 based price fluctuation in the past years.	Very Likely	Marginal	MODERATE	\$73,200,606	Very Unlikely	Negligible	LOW		
	Stakeholders request late changes to project		significant input from stakeholders thru the years have		_	LOW				LOW		 

<sup>\*</sup>Likelihood, Impact, and Risk Level to be verified through market research and analysis (conducted by cost engineer).

- 1. Risk/Opportunity identified with reference to the Risk Identification Checklist and through deliberation and study of the PDT.
- 2. Discussions and Concerns elaborates on Risk/Opportunity Events and includes any assumptions or findings (should contain information pertinent to eventual study and analysis of event's impact to project).
- 3. Likelihood is a measure of the probability of the event occurring -- Very Unlikely, Unlikely, Unlikely, Likely, Very Likely. The likelihood of the event will be the same for both Cost and Schedule, regardless of impact.
- 4. Impact is a measure of the event's effect on project objectives with relation to scope, cost, and/or schedule -- Negligible, Marginal, Significant, Critical, or Crisis. Impacts on Project Cost may vary in severity from impacts on Project Schedule.
- 5. Risk Level is the resultant of Likelihood and Impact **Low**, **Moderate**, or **High**. Refer to the matrix located at top of page.

- 7. The responsibility or POC is the entity responsible as the Subject Matter Expert (SME) for action, monitoring, or information on the PDT for the identified risk or opportunity.
- 8. Correlation recognizes those risk events that may be related to one another. Care should be given to ensure the risks are handled correctly without a "double counting."
- 9. Affected Project Component identifies the specific item of the project to which the risk directly or strongly correlates.

<sup>6.</sup> Variance Distribution refers to the behavior of the individual risk item with respect to its potential effects on Project Cost and Schedule. For example, an item with clearly defined parameters and a solid most likely scenario would probably follow a triangular or norma probability of modeling with respect to effects on cost or schedule (i.e. "anyone's guess") would probably follow a uniform or discrete uniform distribution.

- 10. Project Implications identifies whether or not the risk item affects project cost, project schedule, or both. The PDT is responsible for conducting studies for both Project Cost and for Project Schedule.11. Results of the risk identification process are studied and further developed by the Cost Engineer, then analyzed through the Monte Carlo Analysis Method for Cost (Contingency) and Schedule (Escalation) Growth.