

Inner Harbor Navigational Canal Lock Replacement- Shallow Draft GRR

Annex 3: COST ENGINEERING

February 4th, 2016

Prepared by MVN ED Cost Section

**INNER HARBOR NAVIGATION CANAL
LOCK REPLACEMENT (SHALLOW DRAFT LOCK)
FEASIBILITY STUDY**

COST ENGINEERING APPENDIX

Contents

Cost Estimate 4

Section 1. Cost estimate development 4

Section 2. Estimate Structure: 4

Section 3. Bid competition: 4

Section 4. Contract Acquisition Strategy: 4

Section 5. Labor Shortages: 4

Section 6. Labor Rates: 4

Section 7. Materials: 4

Section 8. Equipment: 5

Section 9. Fuel: 5

Section 10. Crews: 5

Section 11. Unit Prices: 6

Section 12. Relocation Cost: 6

Section 13. Mobilization: 6

Section 14. Field Office Overhead: 6

Section 15. Overhead assumptions may include: 6

Section 16. Home Office Overhead: 7

Section 17. Taxes: 7

Section 18. Bond: 7

Section 19. E&D and S&A: 7

Section 20. Contingencies: 7

Section 21. Escalation: 7

Section 22. HTRW: 8

Section 23. Cost Estimates for Final Array of Alternatives: 8

Schedule 8

Cost Estimate

Section 1. Cost estimate development

- a) The project cost estimate was developed in the MCACES MII cost estimating software and used the standard approaches for a feasibility estimate structure regarding labor, equipment, materials, crews, unit prices, quotes, sub- and prime contractor markups. This philosophy was taken wherever practical within the time constraints. It was supplemented with estimating information from other sources where necessary such as the previous report from 1997, quotes, bid data, and A-E estimates. The intent was to provide or convey a “fair and reasonable” estimate that which depicts the local market conditions. The estimates assume a typical application of tiering subcontractors. Given the long time over which this project/program is to be constructed and the unknown economic status during that time, demands from non-governmental civil works projects were not considered to dampen the competition and increase prices.

Section 2. Estimate Structure:

- a) The estimate is structured to reflect the projects performed. The estimate has been subdivided by USACE feature codes that include levees, floodwalls, a lock structure, pipeline relocations, and a bridge.

Section 3. Bid competition:

- a) It is assumed that there will not be an economically saturated market and that bidding competition will be present.

Section 4. Contract Acquisition Strategy:

- a) It is assumed that the contract acquisition strategy will be similar to past projects with large unrestricted design/bid/build contracts. There are no declared contract acquisition plan/types at this time.

Section 5. Labor Shortages:

- a) It is assumed there will be a normal labor market.

Section 6. Labor Rates:

- a) Local labor market wages are above the local Davis-Bacon Wage Determination and actual rates have been used. This is based upon local information and payroll data received from the New Orleans District Construction Representatives and estimators with experiences in past years.

Section 7. Materials:

- a) Cost quotes are used on major construction items when available. Recent quotes may include concrete, steel and concrete piling, rock, gravel and sand. Assumptions include:
 - i) Borrow - Materials will be purchased as part of the construction contract. The estimate does anticipate contractor furnished materials for borrow. Prices include delivery of materials.
 - ii) Concrete - will be purchased from commercial batch plants.

- iii) Steel – Material will be fabricated by know suppliers.
- b) The borrow quantity calculations followed the MVN Geotechnical guidance:
- c) Hauled Levee: 10 BCY of borrow material = 12 LCY hauled = 8 ECY compacted.
- d) An assumed average one-way haul distance of 21 miles was used based upon the local Contractor Furnished pit.
- e) Haul speeds are estimated using 40 mph speed average given the long distances and rural areas.
- f) Rock and stone - The New Orleans delta area has no rock sources. Historically, rock is barged from northern sources on the Mississippi River. This decision is based upon local knowledge, experience and supported with cost quotes.

Section 8. Equipment:

- a) Rates used are based from the latest USACE EP-1110-1-8, Region III. Adjustments are made for fuel and facility capital cost of money (FCCM). Judicious use of owned verses rental rates was considered based on typical contractor usage and local equipment availability. Only a few select pieces of marine \ marsh equipment are considered rental. Full FCCM/Cost of Money rate is latest available; MII program takes EP recommended discount, no other adjustments have been made to the FCCM.
- i) Trucking: The estimate assumed independent self-employed trucking subcontractors due to the large numbers of trucks required.
- ii) Dozers: dozers of the D-5/D-6 variety were chosen based on historical knowledge. Heavier equipment gets mired in the mud and soft soils.
- iii) Rental Rates: Rental rates were used for marsh equipment where rental is typical such as marsh backhoes.

Section 9. Fuel:

- a) Fuels (gasoline, on and off-road diesel) were based on local market averages for on-road and off-road for the Gulf Coast area. The Team found that fuels fluctuate irrationally; thus, used an average.

Section 10. Crews:

- a) Major crew and productivity rates were developed and studied by senior USACE estimators familiar with the type of work. All of the work is typical to the New Orleans District. The crews and productivities were checked by local MVN estimators, discussions with contractors and comparisons with historical cost data. Major crews include clearing and grubbing, hauling, earthwork, piling and concrete.

- b) Most crew work hours are assumed to be 10 hrs 6 days/wk which is typical to the area.

Section 11. Unit Prices:

- a) The unit prices found within the various project estimates will fluctuate within a range between similar construction units such as floodwall concrete, earthwork, and piling. Variances are a result of differing haul distances, small or large business markups, subcontracted items, designs and estimates by others.

Section 12. Relocation Cost:

- a) Relocation costs are defined as the relocation of utilities required for project purposes. In cases where potential significant impacts were known, costs were included within the cost estimate. The St. Claude Bridge is to be relocated as part of this project. Costs related to relocations were taken from the '97 report and escalated to current prices due to constraints in time.

Section 13. Mobilization:

- a) Contractor mobilization and demobilization are based on the assumption that most of the contractors will be coming from within the Gulf Coast/Southern region. Mob/demob costs are based on historical studies of detailed Government estimate mob/demobs which averaged 4.9 to 5% of the construction costs. With undefined acquisition strategies and assumed individual project limits for the large number of potential contracts in this program, the estimate utilizes a more comprehensive approx. 5% value applied at each contract rather than risking minimizing mob/demob costs by detailing costs based on an assumed number of contracts. The 5% value also matches well with the 5% value previously prescribed by Walla Walla District, which has studied historical rates.

Section 14. Field Office Overhead:

- a) The estimate used a field office overhead rate of 7% for the prime contractors at budget level development. Based on historical studies and experience, Walla Walla District has recommended typical rates ranging from 7% to 11% for large civil works projects; however, the range does not consider possible incentives such as camps, allowances, travel trailers, meals, etc. which have been used previously to facilitate projects. With undefined acquisition strategies and assumed individual project limits for the multiple number of potential contracts in this program, the estimate utilizes a more comprehensive percentage based approach applied at each contract rather than risking minimizing overhead costs by detailing costs based on an assumed number of contracts. The applied rates were previously discussed among numerous USACE District cost engineers including Walla Walla, Vicksburg, Norfolk, Huntington, St. Paul and New Orleans.

Section 15. Overhead assumptions may include:

- a) Superintendent, office manager, pickups, periodic travel, costs, communications, temporary offices (contractor and government), office furniture, office supplies, computers and software, as-built drawings and minor designs, tool trailers, staging setup, camp and kitchen maintenance and utilities, utility service, toilets, safety equipment, security and

fencing, small hand and power tools, project signs, traffic control, surveys, temp fuel tank station, generators, compressors, lighting, and minor miscellaneous.

Section 16. Home Office Overhead:

- a) Estimate percentages range based upon consideration of 8(a), small business and unrestricted prime contractors. The rates are based upon estimating and negotiating experience, and consultation with local construction representatives. The applied rates were previously discussed among numerous USACE District cost engineers including Walla Walla, Vicksburg, Norfolk, Huntington, St. Paul and New Orleans.

Section 17. Taxes:

- a) Local taxes will be applied, using an average between the parishes that contain the work. Reference the LA parish tax rate website: <http://www.laota.com/pta.htm>

Section 18. Bond:

- a) Bond is assumed 1% applied against the prime contractor, assuming large contracts.

Section 19. E&D and S&A:

- a) USACE Costs to manage design (PED) and construction (S&A) are based on New Orleans District Programmatic Cost Estimate guidance:
 - i) Planning, Engineering & Design (PED): The PED cost includes such costs as project management, engineering, planning, designs, investigations, studies, reviews, value engineering and engineering during construction (EDC). Historically New Orleans District has used an approximate 12% rate for E&D/EDC, applied against the estimated construction costs. Other USACE civil works districts such as St. Paul, Memphis and St. Louis have reported values ranging from 10-15%. Additional costs were added for project management, engineering, planning, designs, investigations, studies, reviews, value engineering. Specific PED costs were originally calculated and then that same percentage was carried forward on all future updates.
 - ii) Supervision & Administration (S&A): Historically, New Orleans District used a range from 5% to 15% depending on project size and type applied against the estimated construction costs. Other USACE civil works districts such as St. Paul, Memphis and St. Louis report values ranging from 7.5-10%. Consideration includes that a portion of the S&A effort could be performed by contractors. Based on discussions with MVN Construction Division, an S&A cost based on contract durations was developed. Specific S&A costs were originally calculated and then that same percentage was carried forward on all future updates.

Section 20. Contingencies:

- a) Contingencies were developed using the USACE Abbreviated Cost Risk Analysis (ARA) cost related risks. See summary in Cost Schedule Risk Analysis (CSRA) section.

Section 21. Escalation:

- a) Escalation used in the TPCS is based upon the US Army Corps of Engineers Engineering Manual (EM) 1110-2-1304 Civil Works Construction Cost Index System (CWCCIS) revised 30 Sept 2015.

Section 22. HTRW:

- a) The estimate includes no costs for any potential Hazardous, Toxic, and Radioactive Waste (HTRW) concerns. Some material to be removed from the canal is assumed to be contaminated and will be contained in a Confined Disposal Facility (CDF).

Section 23. Cost Estimates for Final Array of Alternatives:

- a) The preliminary cost estimates were developed during the planning process as a means of evaluating each restoration alternative and for use with the Institute for Water Resources (IWR) analysis. The costs estimated for all alternatives are shown on the section Alternative Formulation Cost Summary. Please note these preliminary costs estimates were used for planning purposes only and do not represent a fully funded costs estimate. These costs include contingencies calculated using the MCX Abbreviated Cost Risk Analysis program.

Schedule

- a) The project schedule was developed based on the construction of the individual features of work which includes the dredging of a channel bypass, canal excavation, construction of a cofferdam, the new IHNC lock, a temporary and new bridge for St Claude, earthen levees and floodwalls.

Alternative Formulation Cost Summary

Abbreviated Risk Analysis

Project (less than \$40M): **Inner Harbor Navigation Canal Lock Replacement**

Alternative: **110' x 1,200' Lock -22 Draft**

Project Development Stage/Alternative: **Alternative Formulation**

Risk Category: **High Risk: Complex Project or Unique Type Construction**

Meeting Date: **No meeting due to time constraints.**

Total Estimated Construction Contract Cost = **\$ 517,488,140**

	<u>CWWBS</u>	<u>Feature of Work</u>	<u>Contract Cost</u>	<u>% Contingency</u>	<u>\$ Contingency</u>	<u>Total</u>
	01 LANDS AND DAMAGES	Real Estate	\$ 633,000	27.17%	\$ 172,000	\$ 805,000
1	02 RELOCATIONS	Relocations	\$ 72,038,965	68.69%	\$ 49,482,020	\$ 121,520,985
2	05 LOCKS	Locks	\$ 310,888,617	54.43%	\$ 169,229,548	\$ 480,118,165
3	09 CHANNELS AND CANALS (Except Navigation Ports and Harbors)	Channels and Canals	\$ 25,010,512	34.69%	\$ 8,676,665	\$ 33,687,177
4	11 LEVEES AND FLOODWALLS	Levees and Floodwalls	\$ 109,502,307	29.02%	\$ 31,774,766	\$ 141,277,073
5				0.00%	\$ -	\$ -
6				0.00%	\$ -	\$ -
7				0.00%	\$ -	\$ -
8				0.00%	\$ -	\$ -
9				0.00%	\$ -	\$ -
10			\$ -	0.00%	\$ -	\$ -
11			\$ -	0.00%	\$ -	\$ -
12	All Other	Remaining Construction Items	\$ 47,739	0.0%	\$ 4,774	\$ 52,512
13	30 PLANNING, ENGINEERING, AND DESIGN	Planning, Engineering, & Design	\$ 62,098,577	15.15%	\$ 9,410,004	\$ 71,508,581
14	31 CONSTRUCTION MANAGEMENT	Construction Management	\$ 51,748,814	14.41%	\$ 7,456,518	\$ 59,205,332
XX	FIXED DOLLAR RISK ADD (EQUALLY DISPERSED TO ALL, MUST INCLUDE JUSTIFICATION SEE BELOW)				\$ -	

Totals						
	Real Estate	\$	633,000	27.17%	\$	172,000
	Total Construction Estimate	\$	517,488,140	50.08%	\$	259,167,774
	Total Planning, Engineering & Design	\$	62,098,577	15.15%	\$	9,410,004
	Total Construction Management	\$	51,748,814	14.41%	\$	7,456,518
	Total	\$	631,968,530	44%	\$	276,206,296

	Base	50%	80%
Range Estimate (\$000's)	\$631,969k	\$797,693k	\$908,175k

* 50% based on base is at 5% CL.

Fixed Dollar Risk Add: (Allows for additional risk to be added to the risk analysis. Must include justification. Does not allocate to Real Estate.)

Abbreviated Risk Analysis

Project (less than \$40M): **Inner Harbor Navigation Canal Lock Replacement**
 Project Development Stage/Alternative: **Alternative Formulation**
 Risk Category: **High Risk: Complex Project or Unique Type Construction**

Alternative: **75' x 1,200' Lock -22 Draft**

Meeting Date: **No meeting due to time constraints.**

Total Estimated Construction Contract Cost = \$ **501,620,170**

	<u>CWWBS</u>	<u>Feature of Work</u>	<u>Contract Cost</u>	<u>% Contingency</u>	<u>\$ Contingency</u>	<u>Total</u>
	01 LANDS AND DAMAGES	Real Estate	\$ 633,000	27.17%	\$ 172,000	\$ 805,000
1	02 RELOCATIONS	Relocations	\$ 72,038,965	68.69%	\$ 49,482,020	\$ 121,520,985
2	05 LOCKS	Locks	\$ 295,453,204	54.43%	\$ 160,827,414	\$ 456,280,618
3	09 CHANNELS AND CANALS (Except Navigation Ports and Harbors)	Channels and Canals	\$ 24,625,694	34.69%	\$ 8,543,164	\$ 33,168,857
4	11 LEVEES AND FLOODWALLS	Levees and Floodwalls	\$ 109,502,307	29.02%	\$ 31,774,766	\$ 141,277,073
5				0.00%	\$ -	\$ -
6				0.00%	\$ -	\$ -
7				0.00%	\$ -	\$ -
8				0.00%	\$ -	\$ -
9				0.00%	\$ -	\$ -
10			\$ -	0.00%	\$ -	\$ -
11			\$ -	0.00%	\$ -	\$ -
12	All Other	Remaining Construction Items	\$ -	0.00%	\$ -	\$ -
13	30 PLANNING, ENGINEERING, AND DESIGN	Planning, Engineering, & Design	\$ 60,194,420	15.15%	\$ 9,121,461	\$ 69,315,881
14	31 CONSTRUCTION MANAGEMENT	Construction Management	\$ 50,162,017	14.41%	\$ 7,227,875	\$ 57,389,892
XX	FIXED DOLLAR RISK ADD (EQUALLY DISPERSED TO ALL, MUST INCLUDE JUSTIFICATION SEE BELOW)				\$ -	

Totals						
	Real Estate	\$	633,000	27.17%	\$	172,000
	Total Construction Estimate	\$	501,620,170	49.96%	\$	250,627,364
	Total Planning, Engineering & Design	\$	60,194,420	15.15%	\$	9,121,461
	Total Construction Management	\$	50,162,017	14.41%	\$	7,227,875
	Total	\$	612,609,608	44%	\$	267,148,700

	Base	50%	80%
Range Estimate (\$000's)	\$612.610k	\$772.899k	\$879.758k

* 50% based on base is at 5% CL.

Fixed Dollar Risk Add: (Allows for additional risk to be added to the risk analysis. Must include justification. Does not allocate to Real Estate.)

Abbreviated Risk Analysis

Project (less than \$40M): **Inner Harbor Navigation Canal Lock Replacement**

Alternative: **110' x 900' Lock -22 Draft**

Project Development Stage/Alternative: **Alternative Formulation**

Risk Category: **High Risk: Complex Project or Unique Type Construction**

Meeting Date: **No meeting due to time constraints.**

Total Estimated Construction Contract Cost = \$ **510,881,526**

	<u>CWWBS</u>	<u>Feature of Work</u>	<u>Contract Cost</u>	<u>% Contingency</u>	<u>\$ Contingency</u>	<u>Total</u>
	01 LANDS AND DAMAGES	Real Estate	\$ 633,000	27.17%	\$ 172,000	\$ 805,000
1	02 RELOCATIONS	Relocations	\$ 72,038,965	68.69%	\$ 49,482,020	\$ 121,520,985
2	05 LOCKS	Locks	\$ 281,011,422	54.43%	\$ 152,966,153	\$ 433,977,575
3	09 CHANNELS AND CANALS (Except Navigation Ports and Harbors)	Channels and Canals	\$ 24,453,506	34.69%	\$ 8,483,428	\$ 32,936,934
4	11 LEVEES AND FLOODWALLS	Levees and Floodwalls	\$ 109,502,307	29.02%	\$ 31,774,766	\$ 141,277,073
5				0.00%	\$ -	\$ -
6				0.00%	\$ -	\$ -
7				0.00%	\$ -	\$ -
8				0.00%	\$ -	\$ -
9				0.00%	\$ -	\$ -
10			\$ -	0.00%	\$ -	\$ -
11			\$ -	0.00%	\$ -	\$ -
12	All Other	Remaining Construction Items	\$ 23,875,327	4.9%	\$ 2,387,533	\$ 26,262,859
13	30 PLANNING, ENGINEERING, AND DESIGN	Planning, Engineering, & Design	\$ 61,305,783	15.15%	\$ 9,289,869	\$ 70,595,653
14	31 CONSTRUCTION MANAGEMENT	Construction Management	\$ 51,088,153	14.41%	\$ 7,361,323	\$ 58,449,475
XX	FIXED DOLLAR RISK ADD (EQUALLY DISPERSED TO ALL, MUST INCLUDE JUSTIFICATION SEE BELOW)				\$ -	\$ -

Totals						
	Real Estate	\$	633,000	27.17%	\$	805,000.00
	Total Construction Estimate	\$	510,881,526	47.97%	\$	755,975,427
	Total Planning, Engineering & Design	\$	61,305,783	15.15%	\$	70,595,653
	Total Construction Management	\$	51,088,153	14.41%	\$	58,449,475
	Total	\$	623,908,462	42%	\$	885,825,555
					Base	50%
	Range Estimate (\$000's)				\$623,908k	\$885,826k

* 50% based on base is at 5% CL.

Fixed Dollar Risk Add: (Allows for additional risk to be added to the risk analysis. Must include justification. Does not allocate to Real Estate.)

Abbreviated Risk Analysis

Project (less than \$40M): **Inner Harbor Navigation Canal Lock Replacement**
 Project Development Stage/Alternative: **Alternative Formulation**
 Risk Category: **High Risk: Complex Project or Unique Type Construction**

Alternative: 110' x 1,200' Lock -16 Draft

Meeting Date: No meeting due to time constraints.

Total Estimated Construction Contract Cost = \$ **508,397,421**

	<u>CWWBS</u>	<u>Feature of Work</u>	<u>Contract Cost</u>	<u>% Contingency</u>	<u>\$ Contingency</u>	<u>Total</u>
	01 LANDS AND DAMAGES	Real Estate	\$ 633,000	27.17%	\$ 172,000	\$ 805,000
1	02 RELOCATIONS	Relocations	\$ 72,038,965	68.69%	\$ 49,482,020	\$ 121,520,985
2	05 LOCKS	Locks	\$ 302,214,326	54.43%	\$ 164,507,772	\$ 466,722,098
3	09 CHANNELS AND CANALS (Except Navigation Ports and Harbors)	Channels and Canals	\$ 24,641,823	34.69%	\$ 8,548,759	\$ 33,190,582
4	11 LEVEES AND FLOODWALLS	Levees and Floodwalls	\$ 109,502,307	29.02%	\$ 31,774,766	\$ 141,277,073
5				0.00%	\$ -	\$ -
6				0.00%	\$ -	\$ -
7				0.00%	\$ -	\$ -
8				0.00%	\$ -	\$ -
9				0.00%	\$ -	\$ -
10			\$ -	0.00%	\$ -	\$ -
11			\$ -	0.00%	\$ -	\$ -
12	All Other	Remaining Construction Items	\$ (0)	0.0%	\$ (0)	\$ (0)
13	30 PLANNING, ENGINEERING, AND DESIGN	Planning, Engineering, & Design	\$ 61,007,691	15.15%	\$ 9,244,698	\$ 70,252,389
14	31 CONSTRUCTION MANAGEMENT	Construction Management	\$ 50,839,742	14.41%	\$ 7,325,529	\$ 58,165,271
XX	FIXED DOLLAR RISK ADD (EQUALLY DISPERSED TO ALL, MUST INCLUDE JUSTIFICATION SEE BELOW)				\$ -	\$ -

Totals								
	Real Estate	\$	633,000	27.17%	\$	172,000	\$	805,000.00
	Total Construction Estimate	\$	508,397,421	50.02%	\$	254,313,318	\$	762,710,740
	Total Planning, Engineering & Design	\$	61,007,691	15.15%	\$	9,244,698	\$	70,252,389
	Total Construction Management	\$	50,839,742	14.41%	\$	7,325,529	\$	58,165,271
	Total	\$	620,877,854	44%	\$	271,055,546	\$	891,933,400
				Base		50%		80%
	Range Estimate (\$000's)			\$620,878k		\$783,511k		\$891,933k

* 50% based on base is at 5% CL.

Fixed Dollar Risk Add: (Allows for additional risk to be added to the risk analysis. Must include justification. Does not allocate to Real Estate.)

Abbreviated Risk Analysis

Project (less than \$40M): **Inner Harbor Navigation Canal Lock Replacement**

Alternative: **110' x 1,200' Lock -22 Draft**

Project Development Stage/Alternative: **Alternative Formulation**

Risk Category: **High Risk: Complex Project or Unique Type Construction**

Meeting Date: **No meeting due to time constraints.**

Total Estimated Construction Contract Cost = **\$ 517,488,140**

	<u>CWWBS</u>	<u>Feature of Work</u>	<u>Contract Cost</u>	<u>% Contingency</u>	<u>\$ Contingency</u>	<u>Total</u>
	01 LANDS AND DAMAGES	Real Estate	\$ 633,000	27.17%	\$ 172,000	\$ 805,000
1	02 RELOCATIONS	Relocations	\$ 72,038,965	68.69%	\$ 49,482,020	\$ 121,520,985
2	05 LOCKS	Locks	\$ 310,888,617	54.43%	\$ 169,229,548	\$ 480,118,165
3	09 CHANNELS AND CANALS (Except Navigation Ports and Harbors)	Channels and Canals	\$ 25,058,250	34.69%	\$ 8,693,227	\$ 33,751,477
4	11 LEVEES AND FLOODWALLS	Levees and Floodwalls	\$ 109,502,307	29.02%	\$ 31,774,766	\$ 141,277,073
5				0.00%	\$ -	\$ -
6				0.00%	\$ -	\$ -
7				0.00%	\$ -	\$ -
8				0.00%	\$ -	\$ -
9				0.00%	\$ -	\$ -
10			\$ -	0.00%	\$ -	\$ -
11			\$ -	0.00%	\$ -	\$ -
12	All Other	Remaining Construction Items	\$ -	0.00%	\$ -	\$ -
13	30 PLANNING, ENGINEERING, AND DESIGN	Planning, Engineering, & Design	\$ 62,098,577	15.15%	\$ 9,410,004	\$ 71,508,581
14	31 CONSTRUCTION MANAGEMENT	Construction Management	\$ 51,748,814	14.41%	\$ 7,456,518	\$ 59,205,332
XX	FIXED DOLLAR RISK ADD (EQUALLY DISPERSED TO ALL, MUST INCLUDE JUSTIFICATION SEE BELOW)				\$ -	\$ -

Totals								
	Real Estate	\$	633,000	27.17%	\$	172,000	\$	805,000.00
	Total Construction Estimate	\$	517,488,140	50.08%	\$	259,179,561	\$	776,667,701
	Total Planning, Engineering & Design	\$	62,098,577	15.15%	\$	9,410,004	\$	71,508,581
	Total Construction Management	\$	51,748,814	14.41%	\$	7,456,518	\$	59,205,332
	Total	\$	631,968,530	44%	\$	276,218,083	\$	908,186,614
					Base	50%	80%	
	Range Estimate (\$000's)				\$631,969k	\$797,700k		\$908,187k

* 50% based on base is at 5% CL.

Fixed Dollar Risk Add: (Allows for additional risk to be added to the risk analysis. Must include justification. Does not allocate to Real Estate.)

Total Project Cost Summary (TPCS)

This section will present the Total Project Cost Sheet for the Tentatively Selected Plan.

MII Cost Estimate

This section will present the MII Cost Report Summary for the Tentatively Selected Plan.

Project Construction Schedule

Activity ID	Activity Name	Original Duration	Start	Finish	Total Float	2020-2029																											
						Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3
Total		3596	01-Oct-19	05-Aug-29	0																												
IHNC Shallow Draft		3596	01-Oct-19	05-Aug-29	0																												
Relocations		3596	01-Oct-19	05-Aug-29	0																												
A1210	St. Claude Temporary Bridge	913	01-Oct-19	01-Apr-22	0	St. Claude Temporary Bridge																											
A1220	St. Claude Permanent Bridge	1095	06-Aug-26	05-Aug-29	0																												
Locks		1628	28-Jan-20	14-Jul-24	1848	14-Jul-24, Locks																											
A1040	Mobilization and Submittals	45	28-Jan-20	13-Mar-20	1848	Mobilization and Submittals																											
A1045	Temp Dolphins	2	13-Mar-20	15-Mar-20	1848	Temp Dolphins																											
A1050	Cofferdam (750 days / 2 crews)	200	15-Mar-20	01-Oct-20	1848	Cofferdam (750 days / 2 crews)																											
A1060	Earthwork (550 Days / 2 crews)	275	01-Oct-20	03-Jul-21	1848	Earthwork (550 Days / 2 crews)																											
A1070	Pile driving (889 Days / 2 crews)	445	03-Jul-21	21-Sep-22	1848	Pile driving (889 Days / 2 crews)																											
A1080	Concrete	185	21-Sep-22	25-Mar-23	1848	Concrete																											
A1085	Buildings and Control House	200	25-Mar-23	11-Oct-23	1848	Buildings and Control House																											
A1090	Install gates	14	27-Sep-23	11-Oct-23	1848	Install gates																											
A1095	Remove Temp Structures	125	11-Oct-23	13-Feb-24	1848	Remove Temp Structures																											
A1100	Timber Walls	150	13-Feb-24	12-Jul-24	1848	Timber Walls																											
A1110	Demobilization	2	12-Jul-24	14-Jul-24	1848	Demobilization																											
Channels and Canals		2521	01-Oct-19	25-Aug-26	1075	25-Aug-26, Channels and Canals																											
New Lock Channel Excavation		120	01-Oct-19	28-Jan-20	1848	28-Jan-20, New Lock Channel Excavation																											
A1000	Mobilization	30	01-Oct-19	31-Oct-19	1848	Mobilization																											
A1005	CDF Retention Dikes	68	31-Oct-19	07-Jan-20	1848	CDF Retention Dikes																											
A1010	New Lock Channel and Bypass Dredg	20	07-Jan-20	27-Jan-20	1848	New Lock Channel and Bypass Dredging																											
A1030	Demobilization	2	27-Jan-20	28-Jan-20	1848	Demobilization																											
Old Lock Channel Excavation		115	03-May-26	25-Aug-26	1075	25-Aug-26, Old Lock Channel Excavation																											
A1230	Mobilization	30	03-May-26	02-Jun-26	0	Mobilization																											
A1240	New Lock Channel and Bypass Dredg	5	02-Jun-26	07-Jun-26	0	New Lock Channel and Bypass Dredging																											
A1260	Bank Stabilization	78	07-Jun-26	24-Aug-26	1075	Bank Stabilization																											
A1270	Demobilization	2	24-Aug-26	25-Aug-26	1075	Demobilization																											
Levees and Floodwalls		1591	01-Apr-22	09-Aug-26	1092	09-Aug-26, Levees and Floodwalls																											
A1120	Mobilization and Submittals	30	01-Apr-22	01-May-22	0	Mobilization and Submittals																											
A1130	Pile tests	30	01-May-22	31-May-22	0	Pile tests																											
A1140	Embankment	35	31-May-22	05-Jul-22	0	Embankment																											
A1150	Pile driving	280	05-Jul-22	11-Apr-23	0	Pile driving																											
A1160	Concrete Floodwall (328 Monoliths)	1148	11-Apr-23	02-Jun-26	0	Concrete Floodwall (328 Monoliths)																											
A1180	Demolition of existing Floodwall	35	07-Jun-26	12-Jul-26	1117	Demolition of existing Floodwall																											
A1190	Demolition of Existing Buildings	60	07-Jun-26	06-Aug-26	0	Demolition of Existing Buildings																											
A1200	Demobilization	3	06-Aug-26	09-Aug-26	1092	Demobilization																											

█ Actual Work █ Critical Remaining Work Summary
 Remaining Work ◆ Milestone



Cost and Schedule Risk Analysis (CSRA)

A Cost and Schedule Risk analysis will be prepared alongside a report once a Tentatively Selected Plan has been chosen. This section will serve as a summary of the Risk report.